

Project Owner:	Kentwood Public Schools
Project Name:	Classroom Multimedia Systems
Issue Date:	February 1, 2022

PROJECT QUESTIONS AND ANSWERS

*This document provides answers to questions asked by bidders who have reviewed the **Technology Request for Bid** for the above referenced project.*

Q1: On your riser diagram, you indicate projector transmitter/control pad. I don't see this in the spec. Are you looking for an interface to control both audio and or the projector? You show this at the teacher location. Is raceway also required?

A: This unit is included with the 1485fi project and will be installed by Contractor. Raceway will be provided by Others.

Q2: You also say on page 27 41 1600-39 2.12 HDMI transmission equipment installation only. What is the product? Is raceway required? Can you please indicate manufacture and model being provided by district.

A: Epson 1485fi projectors come with a HDBaseT control pad with power supply. Information regarding the capabilities of this system can be found on the Epson website.

Q3: Please provide a flow diagram / line diagram on total intent.

A: See appendix C of original bid documents.

Q4: The school is providing the projectors – do that include the mounts as there was no specification calling out a mount.

A: Mounts will be provided by Owner.

Q5: On the Kentwood Multimedia installation project, I don't see a mention of the cable that connects the projector to the wall plate needing to be plenum. Usually you specify a plenum cable and maybe I read right over it.

A: See page 35 (section 2.04 and 205) for clarification.

Q6: 2.10 – Wireless Presentation System – Section C - Contractor shall provide all necessary licensing for cloud management of all Kramer VIA GO2 wireless presentation system. Contractor shall fully configure all Kramer VIA GO2 wireless presentation devices to be connected to Owner provide network and configured in provided cloud management system. Q: For how long? VSM Cloud Subscription is 1, 3, or 5 year per device.

A: Term of service of VSM cloud management should run concurrently to system warranty, 3 years.

Q7: I am trying to figure out in the documents when the start date and projected end date of the project is.

<i>Bid ID: 2731</i>	Communications by Design, Inc.
<i>Questions and Answers Issued: February 14, 2022</i>	<i>Proprietary Information – All Rights Reserved</i>

A: See page 50 of the original bid documents. This was discussed at length during the pre-bid meeting. The intent is to have the work completed as soon as possible but construction and equipment availability will dictate schedules.

END OF QUESTIONS AND ANSWERS #1

<i>Bid ID: 2731</i>	Communications by Design, Inc.
<i>Questions and Answers Issued: February 14, 2022</i>	<i>Proprietary Information – All Rights Reserved</i>