

<b>Project Owner:</b>	Battle Creek Public Schools
<b>Project Name:</b>	NWMS Building Access Control System
<b>Issue Date:</b>	May 10, 2023

## ADDENDUM NO. 1

*This Addendum No. 1 of the Technology Request for Bid for the above referenced project hereby amends, supplements and/or augments all prior issued document(s) as described herein, and becomes an inseparable part of the Contract Documents, superseding all previous, contrary and/or conflicting information.*

<b>AD1 - 1</b>	Appendix A: Building Access Drawing is hereby revised, reissued and attached hereto.
----------------	--

END OF ADDENDUM NO. 1



APPENDIX A - BUILDING ACCESS SYSTEM DRAWING

ADDENDUM 1  
DATED 5.25.2023

GENERAL NOTES:

1. SUB-CONTRACTORS ARE TO COORDINATE WORK WITH ALL OTHER TRADES.
2. CONFLICTS BETWEEN NOTES, DETAILS, SPECIFICATIONS, ETC., SHALL BE VERIFIED WITH THE OWNER'S REPRESENTATIVE OR THE MOST STRINGENT PROVISIONS SHALL GOVERN.
3. DETAILS OF CONSTRUCTION NOT FULLY SHOWN SHALL BE OF THE SAME NATURE AS SHOWN FOR SIMILAR CONDITIONS. ANY UNCLEAR CONDITIONS SHALL BE VERIFIED WITH OWNER'S REPRESENTATIVE PRIOR TO CONSTRUCTION OF THAT AREA.
4. DRAWINGS ARE NOT TO BE SCALED. ANY UNCLEAR DIMENSIONS OR DIMENSIONAL DISCREPANCIES SHALL BE VERIFIED WITH OWNER'S REPRESENTATIVE.
5. ALL EXISTING CONDITIONS AND ALL RELATED DIMENSIONS INDICATED IN THE CONTRACT DOCUMENTS SHALL BE FIELD VERIFIED PRIOR TO FABRICATION, ERECTION, AND/OR CONSTRUCTION, ANY CONDITIONS THAT DIFFER FROM THAT INDICATED IN THE CONTRACT DOCUMENTS SHALL BE SUBMITTED TO THE OWNER'S REPRESENTATIVE FOR REVIEW PRIOR TO FABRICATION, ERECTION, AND/OR CONSTRUCTION.
6. CONSTRUCTION MANAGER (CM) / GENERAL CONTRACTOR (GC) TO REVIEW ENTIRE SET OF CONSTRUCTION DOCUMENTS AND SHALL COORDINATE WORK BETWEEN ALL TRADES. IF CONFLICTS ARISE DUE TO COORDINATION OF TRADES, CM / GC IS TO VERIFY CONFLICT WITH OWNER'S REPRESENTATIVE PRIOR TO CONSTRUCTION / INSTALLATION OF CONFLICTING ITEMS.
7. PATCH ALL EXPOSED INTERIOR AND EXTERIOR WALLS WHERE ATTACHED OR IMBEDDED ITEMS WERE REMOVED.
8. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PREPARATION OF ALL SURFACES AS REQUIRED TO RECEIVE NEW FINISHES.
9. ALL DIMENSIONS ARE FROM FACE OF STUD. C.M.U. OR CONCRETE. U.N.O.
10. PROVIDE ISOLATION MATERIAL BETWEEN DISSIMILAR MATERIALS THAT ARE IN CONTACT WITH ONE ANOTHER.
11. PATCH & REPAIR ALL MAJOR & MINOR BLEMISHES AS REQ'D. DUE TO DEMOLITION WORK. MATCH ADJACENT MATERIAL & COLOR.

TECHNOLOGY NOTES:

1. 27 10 00 Contractor to provide data CAT6 data cabling for all locations located on the walls as indicated on drawings.
2. Data cabling in center of classrooms indicated as 5D shall be four (4) CAT6 data cables and one (1) CAT6A data cable for future Access Point.
3. All data cabling shall be plenum rated.
4. 27 41 16 Contractor shall install equipment listed per specification in the new classroom addition.
5. Existing classroom and remodeled classroom audio visual equipment and projection screens will be removed by other and reinstalled by the same contractor.
6. 27 41 16 Contractor shall supply and install projection and screen per specification for Dance, Choir and Band Room. See Appendix #.
7. 27 51 16 Contractor shall remove existing public address speakers and reinstall according to construction phasing plan.
8. 27 51 16 Contractor to remove all head and equipment located in the MDF and replace with a new system. New system shall integrate existing and new speakers.
9. 27 53 13 Contractor shall remove of and dispose of all existing clocks and associated cabling to source. Contractor to install new clock system head and in MDF. All demolished clocks are to be replaced with new clocks as part of this contractors scope. Contractor to supply all necessary cabling for new clock system.
10. 28 13 00 Contractor to reference Appendix H for Door Hardware Schedule.

SYMBOL LEGEND	
	EXISTING DATA DROP (COUNT)
	EXISTING PROJECTOR
	EXISTING PROJECTION DATA DROP
	EXISTING PROJECTION SCREEN
	EXISTING CLOCK
	EXISTING PUBLIC ADDRESS SPEAKER - DOUBLE SIDED
	EXISTING PUBLIC ADDRESS SPEAKER - DOUBLE SIDED
	EXISTING PUBLIC ADDRESS HORN
	EXISTING PUBLIC ADDRESS CALL BUTTON
	EXISTING CLASSROOM SOUND SPEAKER
	EXISTING WIRELESS ACCESS POINT
	NEW DATA DROP WALL
	NEW DATA DROP CEILING (COUNT, CABLE COILED IN CEILING)
	NEW CLOCK - SINGLE SIDED
	NEW CLOCK - DOUBLE SIDED
	NEW PROJECTOR
	NEW PROJECTION TEACHER STATION
	NEW PROJECTION SCREEN
	NEW CLASSROOM SOUND SPEAKER
	NEW PUBLIC ADDRESS SPEAKER CEILING (2X2)
	NEW CALL PUBLIC ADDRESS CALL BUTTON
	NEW STROBE LIGHT

SYMBOL LEGEND CONTINUED	
	DOOR NUMBER
	EXISTING ACCESS CONTROL PANEL
	EXISTING CARD READER
	EXISTING ELECTRIC STRIKE - SURFACE MOUNT
	EXISTING ELECTRIC STRIKE
	EXISTING MAG LOCK
	EXISTING DOOR CONTACT
	EXISTING REQUEST TO EXIT MOTION SENSOR
	NEW CARD READER - HD SMD 40
	NEW CARD READER - HD SMD 20
	NEW ELECTRIC STRIKE - SURFACE MOUNT
	NEW ELECTRIC STRIKE
	NEW MAG LOCK
	NEW DOOR CONTACT
	NEW MOTION REQUEST TO EXIT MOTION SENSOR
	NEW DOOR RELEASE BUTTON
	NEW LOCKDOWN BUTTON
	NEW P DOOR INTERCOM - DOOR STATION - EXTERIOR
	NEW P DOOR INTERCOM - MASTER STATION - INTERIOR
	NEW PUSH TO ENTER BUTTON

ADDENDUM 1  
DOOR WILL BE ADDED AS A1 ALTERNATE

ADDENDUM 1  
CHANGE TO A1 ALTERNATE ADD  
CONSTRUCTION WILL REMOVE CARD READER

ADDENDUM 1  
A1 ALTERNATE ADD.  
ADD DOOR CONTACT.

ADDENDUM 1  
A1 ALTERNATE ADD.  
ADD OVERHEAD DOOR CONTACT.  
EXAMPLE: INTERLOGIX 2327A-L RAIL  
MOUNT OVERHEAD DOOR CONTACT -  
ARMORED CORD - 3" RAIL

ADDENDUM 1  
A1 ALTERNATE ADD.  
ADD DOOR CONTACTS TO BOTH DOORS.

ADDENDUM 1  
REMOVE PTE FROM SCOPE

ADDENDUM 1  
REMOVE PTE FROM SCOPE

ADDENDUM 1  
REMOVE CARD READER FROM SCOPE

ADDENDUM 1  
REMOVE EXTERIOR AND INTERIOR  
CARD READER FROM SCOPE

FIRST FLOOR OVERALL FLOOR PLAN  
1/16" = 1'-0"

BATTLE CREEK PUBLIC SCHOOLS  
NORTHWESTERN SCHOOL ADDITIONS AND RENOVATION

FLOOR PLAN - OVERALL

ADDENDUM 1  
DATED 5.25.2023

PROJ. #: 21-0458  
DATE: 10-MAY-2023

SHEET

A-101

100% CONSTRUCTION DOCUMENTS