

Project Q & A

Project Owner:	DeWitt Public Schools
Project Name:	Video Monitoring Renovations
Issue Date:	September 22, 2023

Project Questions and Answers:

This document provides answers to questions asked by bidders who have reviewed the Technology Request for Bid for the above referenced project.

Q1	For the Genetec Synergis access control configuration, is it desired to include Active Directory, or some other authoritative data source, integration to automate cardholder management? For example, automatically importing cardholder information as well as credential management (i.e. access right assignment/revocation, activation/deactivation of credentials, or updating data associated with faculty as it changes in Active Directory or other external data source).
A1	Active Directory integration is required for user authentication and access groups only.
Q2	Is it possible to have the location/site names added to the floorplans of Appendix B?
A2	See Addendum 1.
Q3	Can you update the drawings with the locations of the MDF/IDF locations to estimate where the new cabling should terminate?
A3	See Addendum 1.
Q4	Can we have an export of the design file from Axis Site Designer with the requested changes? If this isn't possible, will you provide a legend for the camera types based on the color of the icons so we know which types are to be used and where?
A4	See Addendum 1.
Q5	Is the customer open to a tailored proactive service agreement that enables authorized engineers to remotely access the system for health checks on a more frequent basis than once per year? As an example, these health checks could include verifying recording settings, disk space availability, system log analysis, camera firmware updates, software patches, and operating system updates.
A5	Please provide this as an alternate configuration for Owner consideration.

Q6	There is a discrepancy between Appendix A camera counts for camera Type D-P3719-PLE. The floorplan designs in Appendix B show 12 Type D but the quantity listed in Appendix A is 11. Which one takes precedence?
A6	See Addendum 1.
Q7	For the Low voltage cabling, Is Commscope Uniprise acceptable or does it need to be Commscope Systimax?
A7	Commscope Uniprise.
Q8	Does school requires Systimax or Uniprise for their cabling preference?
A8	See Q7.
Q9	For the Maintenance building (teal building on pg. 93 of RFP) there are existing locations on the building for cameras (see attached). We recently cabled this building. You could either move the camera placement to the locations of the data drops or we can possibly move the data locations to where they are on the map.
A9	Final locations of cameras will be adjusted as necessary
Q10	Is there a quantity that can be supplied identifying how many lockdown buttons there are per building?
A10	Contractors can contact Rebecca Szilagy at rszilagy@cbdconsulting.com for the full Owner documentation set. Contractors making relevant requests as part of this Q and A process will be sent existing documentation.
Q11	Is there a quantity that can be supplied identifying how many release buttons there are per building?
A11	See Q10.
Q12	Are there any doors that are currently being monitored for prop/force that will need to be programmed into the Genetec system as part of this bid?
A12	See Q10.
Q13	Is there a preferred method of supplying Cloudlinks by building or to their max capacity district-wide?
A13	By building.
Q14	Can clarity be given on training required for the system administrators? Specification says to provide mfr certification training for (2) administrators - As a point of clarification, this cost should be incurred by prospective bidders but technical certification will

	ultimately be held by District Administrators, correct? This question is in duplicate for the Synergis technical certification as well.
A14	Correct.
Q15	Drawings within the appendix do not have the building names on them; Can the building names be provided?
A15	See Addendum 1.
Q16	Can the Site Designer Tool/Project be shared? This would help determine which cameras in the appendix are of a certain type; it would also help to understand the server sizing/calculation estimates.
A16	See Addendum 1.
Q17	If the Site Designer tool is not shared, can the Camera Types and their colors be identified as they relate to Appendix A and B? E.g. Cameras in red on the interior are clearly Type D, the purple symbols with the video door stations are self-explanatory, but clarifying Type A, B, E, and F on the drawings will help ensure correct mounting hardware is provided at each location.
A17	See Addendum 1.
Q18	Analytics - within several camera model types there is a reference to the camera being required to have Object Analytics. Is the requirement for the base bid to also provide all necessary programming for configuring the Axis plug-in within Genetec (and vice versa for the Hanwha voluntary alternate)?
A18	Contractor shall configure any necessary analytic plugins as part of base bid configuration.

END OF QUESTIONS AND ANSWERS #1