Technology Request for Bid

Woodhaven-Brownstown School District



Bid ID: 3016 Issue Date: January 5, 2024

SECTION 00 01 10 TABLE OF CONTENTS

DIVISION 00 – BIDDING & CONTRACT REQUIREMENTS

<u>Section</u>	<u>Description</u>
00 01 01	Cover Page
00 01 10	Table of Contents
00 01 15	List of Drawings
00 11 16	Invitation to Bid
00 40 00	Bid Forms
00 21 13	Instructions to Bidders
00 65 00	Contract Close-out

DIVISION 27 – TECHNOLOGY SYSTEMS

<u>Section</u>	<u>Description</u>

27 41 16 Multimedia Systems

APPENDICES Section

Section	<u>Description</u>
A	Woodhaven High School Band & Choir
В	Patrick Henry Middle School Small Gym
C	Woodhaven High School Weight Room

END OF SECTION

SECTION 00 01 15 LIST OF DRAWINGS

<u>File/Name</u> <u>Description</u>

Not Used

END OF SECTION

SECTION 00 11 16 INVITATION TO BID

PART 1 - GENERAL

1.01 WORK INCLUDED: DISTRICT MULTIMEDIA UPGRADES

A. Woodhaven-Brownstown School District (Owner) is seeking bids for purchase and installation of associated equipment and installation related to multimedia systems. Proposed systems shall be configured and installed to service Owner's classrooms, public spaces and common areas across multiple facilities, and as described herein.

B. Project: DISTRICT MULTIMEDIA UPGRADES

C. Owner: Woodhaven-Brownstown School District

24821 Hall Road

Woodhaven, Michigan 48183

D. Designer: Communications by Design, Inc.

E. Sites of Work:

Woodhaven High School
 24787 Van Horn Road
 Brownstown, Michigan 48134

 Patrick Henry Middle School 24835 Hall Road Brownstown, Michigan 48134

1.02 GENERAL DESCRIPTION OF PROJECT SEQUENCE

- A. Sequences and dates specified herein are for information only and indicate the plan and intent of the Owner. Actual dates shall be established based on final award of project.
- B. Sequence of operations shall be established by the Contractor within the guidelines established by the Owner as required to meet schedules.
- C. Schedule:
 - 1. Request for Bid Distributed: Friday January 5, 2024
 - 2. Pre-Bid Meeting: Wednesday January 10, 2024 at 1:00pm

- 3. Intent to Bids Due: Friday January 12, 2024 by 5:00pm
- 4. Question and Clarification Deadline: Friday January 12, 2024 by 5:00pm
- 5. Public Bids Due: Friday January 19, 2024 at 10:00am

1.03 TYPES OF BIDS

A. Bids shall be submitted in total and with required detail for each item bid and as is required herein, and include all portions of the work identified for the individual bid package as specified herein. Bids shall be made on unaltered bid forms as included herein. Bidder shall fill in all blank spaces and the bid shall be signed by a legal officer or agent authorized to bind the bidder to a contract.

1.04 PRE-BID CONFERENCE

- A. A pre-bid conference will be held. A discussion of the project and review of bid documents will be followed by a site review and an opportunity to ask questions. Attendance is highly encouraged for all contractors interested in bidding on any components or portions of this project. Attendance at the pre-bid conference will be a factor considered during evaluation of bids.
- B. Time: Wednesday January 10, 2024 at 1:00pm
- C. Location: Woodhaven-Brownstown School District 24821 Hall Road Woodhaven, Michigan 48183
- D. Any drawings identified in the table of contents herein will be distributed and reviewed at this conference.
- E. Physical building inspections of sites of work will be provided for at this time.

1.05 TIME AND PLACE OF BID RECEPTION

- A. Physically sealed bids for the base bid work will be received at the district office and read aloud at a public opening. Bids arriving after the appointed time as determined by the Owner's representative conducting the public opening, shall be returned unopened. Bids will be accepted beginning fortyeight (48) hours prior to the appointed opening time provided they are in sealed packages and addressed as specified herein.
 - 1. Bid Receipt Deadline: Friday January 19, 2024 at 10:00am
 - Location: Woodhaven-Brownstown School District 24821 Hall Road Woodhaven, Michigan 48183

B. Faxed or electronically delivered bids will not be accepted.

1.06 EXAMINATION AND PROCUREMENT OF DOCUMENTS

- A. Specifications and any relevant Drawings may be obtained from the Technology Designer. Contractors may obtain copies by documented request to Communications by Design, Attn: Rebecca Szilagy. Requests may be made by:
 - 1. Writing 4101 Sparks Drive, Grand Rapids, Michigan 49456
 - 2. Email <u>rszilagy@cbdconsulting.com</u>

1.07 BID SECURITY

- A. Bid security equal to five percent (5%) of the total bid amount, must accompany each base bid in accordance with the Instruction to Bidders.
- B. Bid security shall be either a Bid Bond issued by a company licensed in the State of Michigan to furnish bid security or Certified Check made payable to the Owner.

1.08 PERFORMANCE BOND COVERAGE

A. Selected Contractor(s) will be required to provide a performance bond and payment bond in an amount equal to one hundred percent (100%) of the bid amount including any accepted alternates at the Owner's discretion. Such bonds shall be issued by surety licensed by the State of Michigan and acceptable to the Owner.

1.09 OWNER'S RIGHT TO REJECT BIDS

- A. The Owner reserves the right to reject any and/or all bids. The Owner reserves the right to accept a bid, or portion thereof by issuance of a valid purchase order within ninety (90) calendar days following the bid opening. No bids may be withdrawn during this time without the specific approval of the Owner.
- B. Withdrawal of any Bids after the opening time without specific approval by Owner may result in forfeiture of required bid security by Bidder.

1.10 DEFINITIONS

A. "Owner" is intended to mean Woodhaven-Brownstown School District, a general powers school district.

- B. For purposes of this project, the terms "Architect", "Engineer" and "Designer" are used synonymously to refer to Communications by Design, Inc., a Michigan Corporation.
- C. The term "Bidder" refers to any organization properly and accurately submitting a complete "Intent to Bid Form" prior to the required time specified herein and subsequently properly submitting completed set of bid documents as specified herein.
- D. The term "Contractor" herein is a reference to the firm(s) eventually selected by the Owner to provide the intended system(s), or any portion thereof, and fulfill the terms of the contract.
- E. The term Contract is a reference to the collective set of documents, drawings, diagrams, Owner's Purchase Order, Addenda and all other materials as provided for herein defining arrangement between Owner and Contractor.
- F. The term Addenda (or Addendum) are that portion of the Contract consisting of modifications, amendments, deletions or substitutions to the contract documents issued prior to the execution of the Contract.

END OF SECTION

SECTION 00 40 00 BID FORMS

Intent to Bid Form

Complete and submit the following form if you have interest or intend to submit a Bid for this project. Unaltered and completed forms must be received on or before 5:00 PM on Friday January 12, 2024. Only bidders returning a completed "Intent to Bid Form" will be notified of required addenda.

<u>Company Information</u> Name:	
Address Line1:	
Address Line2:	
City, State and Zip Code Primary Contact Information	
Name:	
Phone No.:	
Fax. No.:	
E-Mail Address:	
Portions of the bid for which your Section 27 41 16	ou will be responding: 5 - Multimedia Systems

Submit unaltered and completed form to:
Rebecca Szilagy
Communications by Design, Inc.
rszilagy@cbdconsulting.com

SEALED BID LABEL

Separate, or fold over, the label on the line below, and affix to the exterior of sealed container so information is clearly visible for Bid Submission. ensure label is attached in a manner to prevent accidental removal or defacement. Label shall serve as sole identification for sealed bid at submission.

BID TO:	Woodhaven-Brownstown School District Attention: Lyndsay Johnson-Lemieux 24821 Hall Road Woodhaven, Michigan 48183	
BID FROM:		
PROJECT:	DISTRICT MULTIMEDIA UPGRADES TECHNOLOGY BID #3016	
INCLUDING	Addendum NoDated	
ADDENDA:	Addendum NoDated	
DUE:	January 19, 2024 at 10:00am	

BID FORM

BID TO:			t
BID FROM:			
PROJECT:	DISTRICT MU TECHNOLOG	JLTIMEDIA UPGRADE Y BID #3016	S
work, and having exa referenced, including	mined the site and a , but not limited to, ment, applicable tax	xes and services required for	ments herein, and herein hereby propose to furnish all
Bid Category	Title		
		I	Oollars (\$).
TAXES: Bid sum includes all a ALLOWANCES:			
	applicable allowanc	ce cost(s) as set forth herein.	
COST OF BONDS Bid sum includes cos each in the amount of	t of furnishing a Per		and Material Payment Bond,
ACKNOWLEDGE The following addendincluded in both base	da have been receive	ed, are hereby acknowledged	d, and their execution is
Addendum No	Dated	Addendum No	Dated

<u>ALTERNATES:</u>	
alternate bids as may be selected	ased or decreased in accordance with each of the following d, following procedures stated herein. Voluntary Alternates shown ped in detail on appropriate attachment(s) as referenced herein.
Voluntary Alternate B	
Voluntary Alternate C	
PRINCIPAL SUBCONTRA	ACTORS g Subcontractors are proposed to be used for this project:
As required herein, the followin	ig Subcontractors are proposed to be used for this project.
Legal Name:	Work Proposed
Legal Name:	Work Proposed
BID SECURITY:	
Accompanying this Bid, as requ Check/Cashier's Check/Bidder'	s Bond in the amount of:

payable to the Owner, which it is agreed, shall be retained as liquidated damages, not as a penalty, by the Owner, if the undersigned fails to execute the Contract in conformity with the form of Contract incorporated and referenced herein and fails to furnish specified bonds within ten (10) days after date of issuance of a Letter of Intent to the undersigned.

If awarded the Contract, the undersigned agrees to commence work within ten (10) calendar days after date of issuance of a Purchase Order, which shall be considered as the notice to proceed, and agrees to complete the work in accordance with the schedule herein.

FAMILIAL DISCLOSURE:

Accompanying this Bid, as required herein, is a legally executed and notarized Michigan Familial Disclosure Statement.

EXCEPTIONS:

Bidder takes no exception to terms, conditions, specifications and/or any other requirements herein unless expressly noted, and specifically identified as provided for herein on unaltered Contract Exception form accompanying this Bid.

SIGNATORY AUTHORITY:

The undersigned certifies they are an authorized agent of the bidding entity, and legally able to bind the bidding entity to the terms, conditions and responsibilities of this, and all referenced bid documents. Furthermore, the undersigned acknowledges an understanding that non-compliance of this authority or any other bidding requirements may result in forfeiture of bid security, dismissal of consideration of bid submitted, and/or personal liability against the signatory.

AGREEMENT:

(If Corporation, affix Seal)

The undersigned agree(s) to provide the post-bid information required within ten (10) days after notification of a Letter of Intent and to execute an agreement for work covered by this Bid on the Owner's standard Purchase Order for which terms and conditions are expanded to include all Bidding Documents and subsequent addenda issued thereto.

In submitting this bid, it is understood that the Owner reserves the right to reject any or all bids. It is further agreed that this bid is binding for a period of Ninety (90) days from the opening thereof.

Respectfully submitted,				
Date:				
Firm Name:				
Signed:				
Official Address:				
Telephone Number:				
Primary Contact Email Address:				

BID FORMS 00 40 00 - 12

Michigan Familial Relationship Disclosure Statement

In accordance with Section 1267 of Michigan Revised School Code this sworn and notarized statement of an authorized representative, discloses any familial relationship between the owner and/or any employee of the Bidder, and any member of the project Owner's governing Board(s) or Superintendent(s).

If any conflict of interest is discovered subsequent to submission of bid, written disclosure shall be submitted to the project Owner within seven (7) days of discovery. The project Owner reserves the right to immediately terminate any contract with Bidder upon notification of a conflict of interest. Upon such termination, the project Owner shall compensate Bidder only for the value of any goods or services provided to the Owner prior to such termination as determined by Designer.

(Check only one	Box Below)					
exists between the owner or any employ	It is herby acknowledged and certified by Bidder that <u>no</u> familial relationship exists between the owner or any employee of the Bidder and any member of the project Owner's governing Board(s) or Superintendent(s).					
A familial relationship exists between the and a member of the project Owner's go The person(s) and the relationship(s) are	overning Board(s) or Superintendent(s).					
Bidder	Board or Superintendent					
Bidder Authorized Representative:						
Bidder:						
Representative's Signature:						
Print or Type Name:						
Representative's Title:						
Subscribed and sworn this day of	, 2023.					
In the County of State or	f					
By Notary Public Signature	Seal or Stamp:					
Notary Public Signature						
My commission expires on:						

REFERENCES

Customer name:	 	
Address:		
City/State/Zip:		
Contact name:		
Contact title:		
Phone:		
E-mail:		
Scope of project:	 	
Scope of project.	 	
Date of completion:		
,		
Customer name:		
Address:		
City/State/Zip:		
Contact name:		
Contact title:		
Phone:		
E-mail:		
Scope of project:		
coope of project.		
Date of completion:		
Bato of completion.		
Customer name:		
Address:		
City/State/Zip:		
Contact name:		
Contact title:		
Phone:		
E-mail:		
Scope of project:		
coope of project.		
Date of completion:	 	

IRAN LINKED BUSINESS AFFIDAVIT

All Bids shall be accompanied by a sworn statement disclosing any Iran Linked Business relationship that exists within the owners, including its officers, directors and employees. The undersigned, owner authorized officer of (the bidder), pursuant to Michigan Public Act No. 517 of 2012, the "Iran Linked Business" requirement provided in the Woodhaven-Brownstown School District Proposals hereby represents and warrants that the bidder, including its officers, directors and employees, is not an "Iran Linked Business" within the meaning of the applicable Public Act, and that in the event bidder is awarded a contract as a result of this RFB, the bidder will not become an "Iran Linked Business" at any time during the course of performing under the contract. The bidder further acknowledges that any person who is found to have submitted a false certification is responsible for a civil penalty of not more than \$250,000.00 or 2 times the amount of the contract or proposed contract for which the false certification was made, whichever is greater, the cost of the District investigation, and reasonable attorney fees, in addition to the fine. Moreover, any person who submitted a false certification shall be ineligible to bid on future Requests for Bids for three (3) years from the date that it is determined that the person has submitted the false certification. There is not an "Iran Linked Business" that exists within the bidder and/or owner, officers, directors and employees. Bidder [Company Name] [Signature] [Title] This instrument was acknowledged before me, a Notary Public, in and for _____ County, _____ on this _____ day of ______, 20__, [Notary Public Signature] My Commission expires:

Acting in the County of: _____

CONTRACT EXCEPTIONS

Check one Box					
Bidder takes no exception to, and agrees to comply with all sections, terms, conditions and/or requirements of the Contract Documents.					
Bidder proposes the following exceptions to the Contract Documents:					
Paragraph Number Explanation					
	•				

NOTE:

Exception(s) to any bid sections, terms, conditions and/or requirements deemed excessive for any reason by the Owner and/or Designer may result in disqualification of Bid.

SCHEDULE OF VALUES/BID FORM

(Bidder may submit version of only this form with slight variation. All information in this form is required for each division/category of work being bid. Submit a completed separate form for each division/category of work clearly delineating on the form the division/category of work for that form. Form submitted must materially match below both in content and format. Electronic version of this form for each project section/division/category being bid is required with bid package as Microsoft Excel compatible spreadsheet on a USB drive. Failure to provide appropriate and complete SCHEDULE OF VALUES for each division/category of work, as determined by the Owner and/or Designer, may result in disqualification of Bid.)

J	Bidder: Bid Division:					
ID	Qty	Part Number	Mfg and Description	Unit Cost	Unit Labor Cost	Total Proposed Cost
			PROJECT MANAGEMENT			
			TRAINING			
			BONDS AND INSURANCE			
			GRAND TOTAL			

(Must match base bid)

SECTION 00 21 13 INSTRUCTIONS TO BIDDERS

PART 1 - GENERAL

1.01 OWNERSHIP

A. Bidders prepare and provide bids without any cost to the Owner and/or Designer. Once opened, bids become the sole property of the Owner. Bidders have no claim to, or ownership of bids opened. Bids become subject to all legal statutes including, if applicable, United States and Michigan Freedom of Information Acts and related laws.

1.02 COMPLIANCE

- A. This document establishes the primary system(s) design configuration. The Bidder's bid response shall include all services, supplies, components and equipment required to provide a complete turnkey system(s) which meets or exceeds all specifications for each given bid item being proposed.
- B. Owner prefers to enter into a contract with a single bidder for all materials for completion of this project, but shall consider combinations of portions of bids from various bidders. The Owner reserves the right to award portions of the project to multiple bidders who will be required to cooperate with one another in order to complete the work.
- C. By their response, Bidders agree to comply with all sections, terms, conditions and/or requirements of the contract documents except as expressly noted, and specifically identified by paragraph number on the unaltered Contract Exceptions Bid Form. Exceptions to any bid sections, terms, conditions and/or requirements deemed excessive by the Owner and/or Bid Coordinator may disqualify Bid.
- D. In compliance with the Freedom of Information Act (FOIA), the Owner shall make bid documents available for public review after issuance of purchase order to the successful bidder/s.
- E. In connection with the execution of this Contract, Contractor and any Subcontractors shall not discriminate against any employee or applicant for employment because of race, religion, color, sex, age, or national origin.
- F. Negligence in preparation, improper preparation, errors in, or omissions from Bids shall not relieve Bidder from fulfillment of any and all obligations and requirements of the Contract Documents.
- G. All Bid documents and worksheets must be completed in detail and submitted together on time.

- H. All documents constituting the entire present agreement shall be construed in accordance with and governed by the laws of the State of Michigan.
- I. Designer shall have authority for interpretation of Contract Documents. In the event terms, provisions or any other portion of the Contract Documents is/are in dispute, Designer shall have full and final authority to interpret the Contract Documents, and such interpretation shall be final and binding.
- J. In the event of a conflict between any terms or conditions in any of the documents comprising the entire present Agreement, the terms and conditions set forth in this document shall take precedence.

1.03 NOTICE AND RESPONSE

- A. Upon notification of Bidder being considered as a finalist, the Bidder shall provide to the Owner and Designer, within 48 hours, a current "Dunn and Bradstreet Supplier Evaluation Report" and other documentation as may be required of finalists herein and as requested by Owner and/or Bid Coordinator.
- B. Bidder shall provide timely response to all requests from Designer and/or Owner regarding clarification and/or elaboration concerning, but not limited to its Bid as may be deemed relevant by the Owner and/or Designer.

1.04 PROTECTION AND SAFETY

- A. Contractor shall continuously maintain adequate protection of all Work from damage and shall protect the Owner's property from injury or loss arising in connection with the execution of the Contract. Contractor shall make good any such damage, injury or loss, except such as may be directly caused by agents or employees of the Owner. The Contractor shall adequately protect adjacent property as required by law, by the Contract Documents, or as otherwise required, to cause no damage to them during the execution of the Contract. This requirement shall also apply to structures above and below ground as conditions of the site require.
- B. Contractor shall be solely responsible for, and have control over means, methods, techniques, sequences and procedures for initiating, maintaining and supervising all safety precautions and programs in connection with the performance of the contract. Contractor shall take all necessary precautions for the safety of employees and visitors on the site of the Project and shall comply with applicable provisions of federal, state, and municipal safety laws and building codes to prevent accidents or injury to persons on, about, or adjacent to the premises where the Work is being performed. Contractor shall erect and properly maintain at all times, as required by the conditions and progress of the Work, all necessary safeguards for the protection of workers and the community.

C. Contractor shall vigorously defend any and all suits that may be brought against the Owner by any person and/or entity, whether in the employ of the Contractor or not, for damage to property, and/or injury or death to persons alleged or claimed to have been caused by or through the performance of work.

1.05 DRAWINGS DIAGRAMS AND ILLUSTRATIONS

- A. Drawings, Diagrams and Illustrations are diagrammatic in nature and indicate general arrangement and nature of systems and work included.
- B. Floor plan drawings are provided to assist the contractor in preparing documentation and reports as required herein.

PART 2 - MATERIALS

2.01 VOLUNTARY ALTERNATES AND SUBSTITUTION OF SPECIFIED PRODUCTS

- A. This Request for Bid describes a particular implementation. All Bids must provide pricing on the "base bid" as described herein. Voluntary alternatives providing comparable functionality with significant cost reduction and/or performance enhancement may be proposed. Voluntary alternatives are encouraged, but must be identified as "Voluntary Alternates" and detailed on unaltered Bid Forms contained herein. Voluntary Alternates may be further detailed and/or explained in attachments to the unaltered Bid Forms contained herein. Exceptions to the Request for Bid specifications must be clearly noted and explained for each Voluntary Alternate proposed.
- B. No substitutions of specified products may be made without specific prior authorization by Designer and Owner. Individual bid divisions herein contain particular information related to acceptable manufacturer and product requirements.
- C. Trade-in, equipment/license exchanges or other return allowances may be provided as a voluntary alternate. Trade-in, exchange or other return equipment allowances shall <u>not</u> be included in base bid amount.

PART 3 - EXECUTION

3.01 EXAMINATION OF DOCUMENTS AND SITE

A. Bidders shall carefully examine the Contract Documents and the construction site to obtain first-hand knowledge of existing conditions and requirements. No plea of ignorance of conditions that exist, or any other relevant matter concerning work to be performed in the execution of work will be accepted as justification for failure to fulfill every detail of all requirements as described herein.

3.02 QUESTIONS, INTERPRETATIONS AND ADDENDA

- A. Any bidder finding discrepancies between Drawings, Specifications and/or Bid Documents, or be in doubt as to the exact meaning of any provision or detail shall notify the Designer at once, and before the deadline for Questions and Clarifications. The Designer may then, at their option, issue Addenda clarifying same. The Designer is not responsible for oral instructions, or Bidder's/Contractor's misinterpretations of Drawings, Specifications and/or Bid Documents.
- B. The Designer reserves the right to issue Addenda at any time up to thirty-six (36) hours prior to the scheduled bid opening. All such addenda shall become, upon issuance, an inseparable part of the Specification/Contract Documents. Each bidder shall incorporate within their bid all costs for items listed in any/all Addenda and shall acknowledge receipt and identifying number of each Addendum on the Bid Form and on the outside of the sealed bid container.
- C. Addenda will be forwarded to each bidder who has received a copy of the Bidding Documents and has submitted "Intent to Bid Form" in addition to being posted publicly.

3.03 BID SECURITY, BONDS AND INSURANCE

- A. Bid Security, Performance and Payment Bonds are required on this project.
 - 1. Bid security equal to five percent (5%) of the bid amount must accompany each bid in accordance with the Instruction to Bidders.
 - a. Bid security shall be either a Bid Bond issued by a company licensed in the State of Michigan to furnish bid security or Certified Check made payable to the Owner.
- B. The selected Contractor will be required to provide a performance bond and a payment bond each in an amount equal to one hundred percent (100%) of the bid amount including any accepted alternates at the Owner's discretion.
 - 1. The surety of the performance bond shall remain in effect until all acceptances and final contract close-out requirements herein have been executed by the Owner.
- C. Contractor shall provide, prior to beginning any work at the sites, certificate of insurance for delivery to Owner indicating all required insurance coverage is in force.
 - 1. Workers' Compensation and Employer's Liability Insurance
 - a. Coverage A Statutory

- b. Coverage B \$1,000,000 Per Accident
- 2. Broad Form Comprehensive General Liability Insurance (including Premises, Elevators, Contractor's Protective Liability, Contractual, Products & Completed Operations including Broad Form Extensions).
 - a. Each Occurrence \$1,000,000
 - b. General Aggregate \$2,000,000
 - c. Products & Completed Operation Aggregate \$2,000,000
 - d. Personal Injury & Advertising Injury \$1,000,000
 - e. Fire Legal \$100,000
- 3. Sub-contractors Operations, Products Completed Operations and Contractual Liabilities, plus such excess coverage as may be appropriate for the limits listed.
- 4. Comprehensive Automobile Liability Insurance (owned, hired, and non-owned automobiles).
 - a. Bodily \$1,000,000 each Person and \$1,000,000 each Occurrence
 - b. Property Damage \$1,000,000
- 5. Furnish Owner with Contingent Liability Insurance Policy with coverage and liability limits the same as for Public Liability Insurance specified herein. Designate on policy as assured, only the Owner.
- 6. Furnish Owner with Contingent Property Damage Insurance Policy with coverage and liability limits the same as for Property Damage specified herein. Designate on policy as assured, only the Owner.
- 7. Policies shall include notification clause requiring ninety (90) days written notice to Owner in the event of policy cancellation, expiration, non-renewal, coverage reduction or other material change.
- 8. Contractor shall not commence work under the Contract until after all insurance required herein as been obtained and certificates for such are approved by Owner.
- D. All such bonds and/or insurance shall be issued by surety licensed by the State of Michigan and acceptable to the Owner.
 - 1. Insurance certificate(s) shall be signed by insurance agent licensed in the state of Michigan or a representative of the insurance company.

E. Contractor agrees to indemnify and hold harmless the Owner and Designer, including their agents and employees, from and against all claims, damages, losses and expenses, including, but not limited to, attorney fees arising out of, or resulting from the performance of the work to the fullest extent allowed by law on a comparison basis of fault.

3.04 MODIFICATION AND WITHDRAWL

- A. Bids may be withdrawn and/or changed any time prior to the deadline for submission of bids. Bids may not be withdrawn or changed thereafter and shall be deemed a form offer continuing for ninety (90) calendar days. Bids receive after the deadline for submission will be returned unopened at the Owner's discretion.
- B. Withdrawal of any Bid after the opening time without specific approval by Owner may result in forfeiture of required bid security by Bidder.

3.05 CODES, ORDINANCES, REGULATIONS AND RELATED

- A. All labor and materials shall be furnished and installed in strict accordance with the latest applicable codes, ordinances and regulations of any governing body having jurisdiction over this project.
- B. In the event the quality of labor and materials required by the Drawings and Specifications herein exceeds requirements of current applicable codes, ordinances and regulations, the Drawings and Specifications shall take precedence.
- C. In the event the quality of labor and materials required by current applicable codes, ordinances and regulations having jurisdiction over this project exceeds that of the Drawings and Specifications herein, the applicable codes, ordinances and regulations shall take precedence.
- D. The Contractor shall give all notices and comply with all codes, laws, ordinances, rules and regulations of any authority having jurisdiction, which bears on the performance of its work. This compliance includes, but is not limited to, the Michigan School Safety Initiative (PA129, PA130, PA131 and PA138) if applicable to work being performed.
- E. The Contractor shall pay for all licenses, permits, taxes, and fees required for this project; and shall comply with all federal, state, local and Owner's codes, laws, ordinances, regulations and other requirements applicable to the work specified at no additional cost to the Owner. Contractor shall submit copies of all approved certificates and approvals to the Owner upon receipt.

3.06 SUB-CONTRACTOR AND MATERIAL SUPPLIER

- A. The successful Bidder shall submit to the Owner and Designer a complete list of all sub-contractors and all material suppliers proposed to engage on the work. Sub-contracts shall not be awarded until after they have been approved by the Designer and Owner.
- B. Finalist bidders may be required to submit additional details related to subcontractors and suppliers within forty-eight (48) hours after the bid opening.
- C. Names of any principal sub-contractors must be listed on the Bid Form.
- D. All contracts made by the successful Bidder with Subcontractors shall be covered by the terms and conditions herein. The successful Bidder shall see to it that Subcontractors are fully informed in regard to these terms and conditions, and shall bind all subcontractors to the same terms and conditions. Failure to do so will absolve the Owner from any liability for additional cost due to subcontractor claims for additional cost, time or any claim(s) for additional cost by subcontractor(s).

3.07 BID RESPONSE FORMAT

- A. Bidder shall provide complete Bid copies in two formats as described herein.
 - 1. One (1) Hard copy format responses shall be in a bound tabulated format. Each response shall have tab indicators for each section.
 - 2. One (1) Electronic copy format responses shall be submitted on a USB Drive, readable by a standard Microsoft Windows 10 workstation. Electronic media shall contain separate folders to organize response documentation as described herein. Files submitted electronically shall be *Adobe Acrobat* "PDF" format (SCHEDULE OF VALUES is additionally required to be on the USB drive in the appropriate folder as a spreadsheet and as described herein).
- B. All Bid Response formats shall be clearly externally marked to include, but not be limited to:
 - 1. Bidder identification.
 - 2. Project Owner identification.
 - 3. Project name.
 - 4. Bid submission date.
- C. Bid Responses shall include an index containing copies/PDF of a complete index of documents comprising Bid Response. Responses shall include, but not be limited to the following tabbed/folder sections:

- 1. Section 1 Forms, which shall contain copies/PDF files of all required and completed bid forms.
 - a. BID FORM
 - b. Michigan Familial Relationship Disclosure Statement
 - c. Iranian Linked Business Affidavit
 - d. REFERENCES
 - e. CONTRACT EXCEPTIONS
 - f. SCHEDULE(s) OF VALUES
 - g. BID BOND
- 2. Section 2 Overview, which shall contain copies/PDF files of cover letter and/or executive overview.
- 3. Section 3 Submittals, which shall contain copies/PDF files of all required and voluntary submittals.
- 4. Section 4 Appendices, which shall contain copies/PDF files of other reference materials Bidder wishes to, or is required to submit.

3.08 AWARD OF CONTRACT

- A. The material proposed to be used for the completion of work, and the competency, solvency and responsibility of bidders will receive due consideration before award of contract. In the reception of bids for this work, the Owner incurs no obligation to accept the lowest, or any bid submitted. The right to accept or reject any and all bids or portion thereof is reserved by the Owner. The Owner reserves the right to require testimonial, accounting or legal documents pertaining to the solvency of a Contractor, or any other decision factor the Owner deems appropriate, prior to award of contract.
- B. Owner reserves the right to select individual components from schedule of values independent of installation as may be determined in Owner's best interest. Selected bidder may be required to install selected components provided by others.
- C. Issuance of a Purchase Order by Owner in response to a valid bid shall be a Notice to Proceed, and shall become part of, but not limited to, all terms, conditions and requirements herein. Notice to Proceed shall have the full effect of contract award, and shall make all terms, conditions, requirements and responsibilities of Bidder binding upon issuance. Notice to Proceed, once

issued, shall become an inseparable part of the contract documents herein, and constitute both Bidder and Owner's acceptance of contract.

3.09 TIME, SCHEDULES, PROJECT MANAGEMENT, MEETINGS AND PLANS

- A. Time is of the essence on this project. Award of contracts for this project will be contingent on the bidder's agreement to complete the work on or before the contract completion date stated herein.
- B. All Contractors will commence work in such a manner and at such a time as to expeditiously interface with the work of other Contractors, and will pursue the project diligently to completion. All Contractors will work in a cooperative manner with Owner and other Contractors.
- C. Contractor shall appoint an overall Project Manager acceptable to Owner, with skills and experience deemed appropriate by the Owner for the scope and size of the project. Project Manager shall be responsible for the scheduling of all Contractor resources and attending all project meetings. Upon notification of Bidder being considered a finalist, the Bidder shall submit professional resume of proposed Project Manager within forty-eight (48) hours.
 - 1. Project meetings shall be conducted at Owner's selected and identified location weekly and at Owner's and/or Designer's discretion.
 - 2. Within five (5) days of Notice to Proceed (issuance of a Purchase Order by the Owner), Contractor's Project Manager shall provide to the Owner a critical flow path in the form of a "Gantt Chart" (or equivalent) indicating the proposed sequence of events and approximate beginning and completion dates in accordance with, compliance to, and coordinated with requirements herein.
 - 3. Changes of the Project Manager during the project shall not be acceptable without prior written approval from the Owner.
 - 4. It is the responsibility of the Contractor's Project Manager to schedule work, work out issues, ensure that all required products and services are delivered according to schedule and attend to any other matters required by the Owner in the interest of professional and timely completion of the project.
 - 5. The appointed Project Manager, or a designee acceptable to the Owner, shall be in attendance of all project meetings throughout the term of the project. Failure to do so may be considered a material breach of contract.
 - 6. After a ten (10) business day notice, the Owner reserves the right to request a new Project Manager, when it appears that, in the Owner's sole discretion, the Project Manager is not fulfilling the full responsibilities of

the position. Failure by Contractor to provide adequate Project Manager meeting requirements of the Owner, may result in Contract termination.

3.10 CHANGES IN THE WORK

- A. No changes in work with the effect of either increasing or decreasing in the project value shall be made without specific and prior authorization by the Owner and Designer.
- B. Owner, without invalidating the contract and without notice to any surety, may at any time order extra work or make changes by altering, adding to or deducting from the work, the Contract Sum being adjusted accordingly. All such work shall be authorized by a written Change Order approved by Owner and Contract Designer. Upon receipt of such an order Contractor shall promptly proceed with the work involved. All such work shall be executed under the conditions of the original Contract. Owner authorized change order(s) may be issued at any time prior to Contract close out.
- C. When so directed, Contractor shall promptly submit an itemized estimate and a unit price for performing or deleting such extra or changed work as may be contemplated. Any extensions or reductions of the contract time associated with extra or changed work shall be identified at the time Contractor submits such documentation.
- D. At the Owner's discretion, adjustments in the Contract Sum shall be determined by one or more of the following methods:
 - 1. By mutual acceptance of a lump sum cost, including overhead and profit, itemized and supported by sufficient substantiating data to permit evaluation.
 - 2. By unit prices stated in the Contract Documents including, but not limited to, Schedule of Values.
 - 3. By unit prices mutually agreed upon.

3.11 PAYMENT REQUESTS AND PAYMENTS

- A. Contractor's invoices shall be submitted monthly in correlation with the Project Schedule indicating percentage of work completed.
- B. All contract and change order invoices shall be sent directly to Contract Designer.
- C. A 10% retainage shall be held back on all payment requests, including, but not limited to hardware, software, change orders and services, until final completion and close out of the project or project phase as determined by Owner and Designer.

- D. Contractors are required to submit all invoices on approved AIA Payment Request Forms or other billing format pre-approved by Contract Designer. Each AIA Payment Request Form shall be accompanied by a properly completed, executed and notarized Waiver of Lien which shall be in a format and contain verbiage approved by Owner.
- E. The Contract Designer and Owner shall process payment requests on a monthly schedule and in accordance with their respective established processes and procedures. Payments will be made by the Owner based only on AIA Request Forms having been previously certified, audited and approved by Contract Designer and accompanied by acceptable Waiver of Lien.

END OF SECTION

SECTION 00 65 00 CONTRACT CLOSE OUT

PART 1 - GENERAL

1.01 WORK INCLUDED

- A. Provide an orderly and efficient transfer of the completed work to Owner.
- B. Details affecting work of this Section includes, but is not limited to all other Sections herein and all related Contract Documents.
- C. Activities relative to Contract close-out are described in, but not limited to, this and other Sections of this document.

1.02 SUBSTANTIAL COMPLETION

- A. "Substantial Completion" shall be defined as:
 - 1. All responsibilities of Contractor for all provisions and requirements of all divisions and sections of complete Contract herein, and as amended, are properly and fully completed or properly, accurately and acceptably provisioned for.
 - 2. All systems, equipment, facilities, services, programming and/or components required by all divisions and sections of complete Contract are fully operational, acceptable and useful to the Owner for their intended purposes.
- B. Prior to requesting inspection by Designer to certify Substantial Completion, Contractor shall use adequate means to assure the Work is completed in accordance with the specified requirements and is ready for such inspection.

PART 2 - MATERIALS

2.01 NOT USED FOR THIS SECTION

PART 3 - EXECUTION

3.01 PROCEDURES

- A. Contractor shall submit a written request to Designer indicating they have achieved Substantial Completion of Work.
- B. Within a reasonable time after receipt of the request, Designer will inspect Work to determine status of completion.
- C. Should Designer determine the Work is not substantially complete:

- 1. Designer promptly will so notify Contractor, in writing giving reasons therefore and providing sufficient details to allow Contractor to make corrective actions.
- 2. Contractor shall then expeditiously remedy the deficiencies and notify Designer in writing when ready for re-inspection.
- 3. Designer will re-inspect the Work.
- 4. Excessive re-inspections of Work may result in fees being assessed Contractor.
- D. Should Designer concur the Work is substantially complete:
 - 1. Designer will prepare a letter of Substantial Completion.
 - 2. Designer will submit the letter to Owner and Contractor.
 - 3. Contract shall be deemed "Closed Out" for retainage purposes.
 - 4. Final Acceptance of the system shall be deemed complete.

END OF SECTION

SECTION 27 41 16 MULTIMEDIA SYSTEMS – GRAPHICS LAB

PART 1 - GENERAL

1.01 DESCRIPTION OF PROJECT

- A. Work described in this specification section pertains to new multimedia infrastructure and instructional equipment for Woodhaven-Brownstown School District.
- B. Contractors shall propose Systems and/or components to be deployed using standard procedures and technology components and as specified herein. The system components shall be installed and connected to the owner's existing physical infrastructure and as specified herein.
- C. Contractor shall advise, coordinate and work cooperatively with Owner representatives or owner's designee related to any configuration changes required and/or proposed for Owner's existing physical infrastructure.
- D. Contractor shall work collaboratively with Owner and Designer. Work shall include but not be limited to installation of supplied equipment, removal of existing equipment and full operational capacity of system as specified herein.
- E. The Contractor shall design, engineer, configure, supply, connect, test, document, train Owner representatives and warrant a fully operational and compliant system and/or component connection to the system complete and with full functionality as specified herein.
- F. Contractor shall provide all transportation and delivery services in a timely manner to individual work location(s) at each site of work in preparation for installation activity.
- G. Contractor shall coordinate their installation with other contractors, Designer and the Owner as is appropriate.

1.02 WARRANTY

- A. Complete installation shall be free from defect and/or failure for a period of warranty. Any replacement, upgrade or fix, including labor for any non-conforming or non-operational part of the system shall be fixed and/or replaced at no cost to the Owner.
- B. Manufacturer's warranty shall be provided for all components of the system.

- 1. Any documents and/or submittals required by individual manufacturers for compliance with the standard and/or applicable extended warranty programs shall be provided and submitted for approval by the Contractor.
- 2. Contractor shall submit all documents, apply for warranty or extended warranty certification, and provide a Certificate of Warranty or Extended Warranty as may be applicable from the manufacturer prior to project closeout.
- 3. Standard manufacturer warranty duration and terms shall be identified for each component with bid as well as additional fee required for warranty duration election of each of the following terms:
 - a. Five (5) year parts and labor warranty.
- C. On site services provided under the warranty shall be performed by personnel or representatives of manufacturer of individual components and/or appropriately trained and certified Contractor representatives as herein defined and located within physical proximity to provide response levels deemed acceptable to Owner.
- D. Contractor shall provide the following response times for all malfunctioning equipment:
 - 1. Twenty-four (24) hours or less for matters that render twenty percent (20%) or more of the system unable to maintain normal functionality.
 - 2. Two (2) business days for matters not meeting the above criteria.
 - 3. Response time shall be measured from the time Contractor is notified by Owner to the time work is begun to resolve the matter.
- E. Bidder shall provide current annual maintenance contract pricing, terms and conditions for recommended maintenance programs for all equipment following the specified and included warranty periods as a Voluntary Alternate. This information will be considered by Owner and Designer as part of the bid evaluation process.
- F. System Warranty shall commence on date of substantial completion as certified by Designer and provided for herein. Delivery to work site of materials, physical removal from packaging, issuance of Contractor documents including, but not limited to invoices and/or packing slips, or any event or documentation, not specifically provided for herein, shall have no effect on Warranty or System Acceptance by Owner and/or Designer.

1.03 SUBMITTALS

- A. Submittals shall consist of, but not be limited to, technical cut sheets and detailed information pamphlets on all components of the system to be installed. All cut sheets and submittals shall be distinctly marked to highlight the actual part number of the item being submitted for approval with Bid Proposals.
- B. Shop drawings, data sheets and diagrams shall be submitted by Bidder for approval by Designer with Bid Proposals.
 - 1. Shop drawings, data sheets and diagrams shall show all data relating to structural, electrical, wiring, cross connect, interconnect, equipment arrangement/layout, and any other information deemed significant by the Designer.
 - 2. No work constituting final installation shall be commenced until after approval of shop drawings, data sheets and diagrams by Designer.
- C. Contractor shall provide proof of manufacturer support by photocopy of certification and letter of support from major component manufacturers for this specific project with Bid Proposals.
- D. Equipment or material installed for this project that do not have an approved submittal associated with it, will be removed and replaced with acceptable equipment or material as defined by the Designer. All replacement costs including, but not limited to material and labor, shall be the sole responsibility of the Contractor.
 - 1. The Owner and/or Designer may notify Contractor of any offending situations under this provision allowing Contractor up to forty-eight (48) hours to correct the situation prior to taking other corrective action.
 - 2. The Owner reserves the right to replace unapproved materials and deduct the costs of doing so as defined herein from any amounts that may be due, or become due Contractor.
- E. The Contractor shall submit within ten (10) calendar days after the Notice to Proceed, a schedule that reflects the sequence of activities of the contractor's approach to the execution of and completion of the work. The schedule shall be broken into work areas to provide for a clear identification of the planned progress of the work. Included in the schedule will be a list of tasks with list of deliverables and the percentage of work completed. This schedule shall coincide with progress payments applications dates and projected amounts. All durations shown will be in working days. Applications that generate Microsoft Project compatible files shall be management tools of choice. The timeframe described in the Contractor's Schedule shall represent the Contractor's plan for organizing, directing, managing, controlling, staffing and

executing the work required by the Contract Documents. The district will rely on such schedules to coordinate and otherwise plan the work of the District, other separate contractors, or the District's routine daily work.

1.04 REFERENCE SPECIFICATIONS

- A. All work, products, and materials shall conform with the following standards as applicable for the intended use:
 - 1. EIA/TIA Commercial and Administration Standards
 - 2. NEC
 - 3. IEEE 802
 - 4. IETF RFCs
 - 5. FCC All Applicable Rules and Regulations
 - 6. UL
 - 7. MIOSHA Safety Standards

1.05 CONTRACTOR

- A. The Contractor shall accept complete responsibility for the installation, certification and support of the system and/or components as required herein. Contractor shall be an authorized vendor of all major components.
- B. All work shall be performed and supervised by Project Managers, Engineers and/or Technicians who are qualified to install specified equipment and perform related tests as recommended by the manufacturer and in accordance with the manufacturer's best practices and methods and as required herein.
- C. Project Managers, Engineers and Technicians employed on this project shall be properly and fully trained and qualified by the manufacturer on the installation and testing of the equipment and systems to be installed.
- D. The Contractor shall have a proven track record in comparable system supply, configuration and installation. This must be shown by the inclusion of references of at least three (3) projects involving the supply and/or installation of similar systems completed by the Contractor in the prior two (2) years with the sealed Bid Proposal as provided herein.

PART 2 - PRODUCTS

2.01 Acceptable Manufacturers

- A. Acceptable manufacturers have been provided to comply with a standard for individual components associated with the specified system. Indicated components include particular models and makes currently installed and/or preferred by Owner.
- B. Any system bid shall be based only on acceptable manufacturer's components.
- 2.02 Supply most current version of all products provided.
 - A. Manufacturer shall have five (5) years of experience and history manufacturing similar products to those specified.
 - B. Proposed components shall have been field tested and proven in actual use.
 - C. Prior and/or old versions of products, unless specifically approved and documented by Designer and/or Owner shall not be acceptable.
 - D. In cases where a newer version of hardware or software is available at the time of installation, Contractor shall request clarification from Designer on which version is to be used.
- 2.03 Furnish only new, first-class quality materials and equipment.
- 2.04 All wiring not installed in conduit shall be plenum type cable and shall be so identified with continuous marking.
- 2.05 All connectors and accessories not installed in conduit and installed above finished ceiling shall be plenum rated.
- 2.06 SPECIAL CONFIGURATION LOCATIONS

2.07 Configuration A

- A. Contractor shall supply one (1) of the specified configurations in each of the following locations.
 - 1. High School Band Room
- B. One (1) Projector
 - 1. Acceptable Manufacturer(s)
 - a. Epson
 - 1. V11H992020
 - 2. 4,200 Lumens

- 3. Projector shall have a minimum of Two (2) HDMI ports for connectivity.
- 4. Projector shall have on board wireless presentation capability.
- 5. Contractor shall insure the projector be securely installed and affixed to mounting system and downpipe that is structurally attached to finished ceiling. Contractor shall supply appropriate mount and downpipe to securely and safely extend projector to optimal location for projection onto construction provided whiteboard.
- 6. Projector shall be connected to supplied HDMI input location system receive transmission of signal from supplied input location.
- C. One (1) Large Diaphragm Condenser Microphone
 - 1. Acceptable Manufacturer(s)
 - a. AudioTechnica
 - 1. AT4050
 - b. Nuemann
 - c. Shure
 - d. Or Equal
 - 2. Supplied mic shall be mounted to the teaching wall in a location as to not interfere with the projected image.
 - 3. Microphone shall be connected to contractor provided audio mixer described heir in.
 - 4. Contractor shall provide all audio cabling and mounting hardware to support a fully functioning system.
- D. One (1) Audio Mixer
 - 1. Acceptable Manufacturer(s)
 - a. PreSonus
 - 1. StudioLive16R
 - b. Or Equal
 - 2. Mixer shall have a minimum of Sixteen (16) XLR-1/4" mic/line inputs.

- 3. Mixer shall have a minimum of Two (2) XLR Main outputs.
- 4. Contractor shall provide all cabling and mounting hardware to support a fully functioning system.

E. One (1) Multi-media Input Faceplate

- 1. Input location shall be in the attached office as detailed in Appendix A. Exact location to be determined by Owner.
- 2. All cable, surface mount box, raceway, connectors and necessary components shall be factory manufactured with terminations and connector assemblies fully attached and integral to the cable to industry published quality standards and meet first class performance requirements and as may be specified herein.
 - a. Infrastructure cable to connect projector to a wall plate shall be provided.
 - 1. Active HDMI Digital Video Cable 1 shall be of commercial firstclass quality manufacture and meet or exceed the following requirements:
 - a. 4K HDMI Active Optical Cable or Equal
 - b. Supports 4K@60Hz
 - c. CMP Plenum Rated
 - d. Rated for in wall use
 - b. Wall plate provided shall be constructed of commercial grade stainless steel.
 - 1. Wall plate shall contain connection points for all specified cables
 - c. Cable shall terminate in the following connector gender:
 - 1. Active HDMI Digital Video Cable 1 HDMI Type A 19 pin plug connector to display device.
 - d. Extra deep, double gang, surface mount box shall be provided for integration with contractor supplied stainless-steel faceplate.
- F. Two (2) Amplification Systems shall be provided and installed
 - 1. Acceptable Manufacturer(s)

- a. Crestron
- b. Crown
 - 1. XLI 3500
- c. Harman/JBL
- d. Or Equal
- 2. Two (2) output channels
- 3. 1600 minimum output per channel bridged mono channel
- 4. S/N (20 Hz 20 kHz @ 8 Ohms) > 97 dB
 - a. Contractor shall provide all cabling and mounting hardware to support a fully functioning system.
- G. One (1) Audio Projection Speaker System
 - 1. Acceptable Manufacturer(s)
 - a. Harman/JBL
 - 1. JBL SRX835
 - b. Or Equal
 - 2. System must contain Two (2) Loud Speakers.
 - 3. Loud Speakers shall be permanently mounted with one on each side of the "teaching wall" detailed in Appendix A. Exact location to be determined by Owner.
 - 4. System must be capable of 1600 watts of power each
 - a. Contractor shall supply all cables and accessories for a fully functional system.
 - 5. One (1) input channel
 - 6. One (1) output channel
 - 7. Contractor shall supply all necessary mounting brackets and hardware fully functional system to the owners desired location.
- H. One (1) Audio Recording/Playback System

- 1. Acceptable Manufacturer(s)
 - a. Tascam
 - 1. SSR250N
 - b. Or Equal
- 2. Audio Recorder shall be mounted in contractor provided audio equipment rack on the "teaching wall". Exact location to be determined by Owner.
 - a. Contractor shall supply all cables and accessories for a fully functional system.
- 3. One (1) input channel
- 4. One (1) output channel
- 5. Contractor shall supply all necessary mounting brackets and hardware fully functional system to the owners desired location.
- 6. Contractor shall configure system for instant recording from contractor provided microphone described herein.
- 7. Contractor shall configure system for instant playback from previously recorded audio.
- I. One (1) Equipment Cabinet
 - 1. Acceptable Manufacturer(s)
 - a. Tripp Lite
 - 1. SRW12US33
 - 2. Equipment cabinet shall be 12U in size
 - 3. Contractor shall supply all necessary mounting brackets and hardware fully functional system to the owners desired location.

2.08 Configuration B

- A. Contractor shall supply one (1) of the specified configurations in each of the following locations.
 - a. High School Choir Room
- B. One (1) Projector

- 1. Acceptable Manufacturer(s)
 - a. Epson
 - 1. V11H992020
- 2. 4,200 Lumens
- 3. Projector shall have a minimum of Two (2) HDMI ports for connectivity.
- 4. Projector shall have on board wireless presentation capability.
- 5. Contractor shall insure the projector be securely installed and affixed to mounting system and downpipe that is structurally attached to finished ceiling. Contractor shall supply appropriate mount and downpipe to securely and safely extend projector to optimal location for projection onto construction provided whiteboard.
- 6. Projector shall be connected to supplied HDMI input location system receive transmission of signal from supplied input location.
- C. One (1) Large Diaphragm Condenser Microphone
 - 1. Acceptable Manufacturer(s)
 - a. AudioTechnica
 - 1. AT4050
 - b. Nuemann
 - c. Shure
 - d. Or Equal
 - 2. Supplied mic shall be mounted to the teaching wall in a location as to not interfere with the projected image.
 - 3. Microphone shall be connected to contractor provided audio mixer described heir in.
 - 4. Contractor shall provide all audio cabling and mounting hardware to support a fully functioning system.
- D. One (1) Audio Mixer
 - 1. Acceptable Manufacturer(s)

- a. PreSonus
 - 1. StudioLive16R
- b. Or Equal
- 2. Mixer shall have a minimum of Sixteen (16) XLR-1/4" mic/line inputs.
- 3. Mixer shall have a minimum of Two (2) XLR Main outputs.
- 4. Contractor shall supply all cabling for connecting existing digital piano to contractor provided audio mixer.
- 5. Contractor shall provide all cabling and mounting hardware to support a fully functioning system.
- E. One (1) Multi-media Input Faceplate
 - 1. Input location shall be in the attached office as detailed in Appendix A. Exact location to be determined by Owner.
 - 2. All cable, surface mount box, raceway, connectors and necessary components shall be factory manufactured with terminations and connector assemblies fully attached and integral to the cable to industry published quality standards and meet first class performance requirements and as may be specified herein.
 - a. Infrastructure cable to connect projector to a wall plate shall be provided.
 - 1. Active HDMI Digital Video Cable 1 shall be of commercial firstclass quality manufacture and meet or exceed the following requirements:
 - a. 4K HDMI Active Optical Cable or Equal
 - b. Supports 4K@60Hz
 - c. CMP Plenum Rated
 - d. Rated for in wall use
 - b. Wall plate provided shall be constructed of commercial grade stainless steel.
 - 1. Wall plate shall contain connection points for all specified cables
 - c. Cable shall terminate in the following connector gender:

- 1. Active HDMI Digital Video Cable 1 HDMI Type A 19 pin plug connector to display device.
- d. Extra deep, double gang, surface mount box shall be provided for integration with contractor supplied stainless-steel faceplate.

F. One (1) Audio Mixer

- 1. Acceptable Manufacturer(s)
 - a. PreSonus
 - 1. StudioLive16R
 - b. Or Equal
- 2. Mixer shall have a minimum of Sixteen (16) XLR-1/4" mic/line inputs.
- 3. Mixer shall have a minimum of Two (2) XLR Main outputs.
- 4. Contractor shall provide all cabling and mounting hardware to support a fully functioning system.
- G. Two (2) Amplification Systems shall be provided and installed
 - 1. Acceptable Manufacturer(s)
 - a. Crestron
 - b. Crown
 - 1. XLI 3500
 - c. Harman/JBL
 - d. Or Equal
 - 2. Two (2) output channels
 - 3. 1600 minimum output per channel bridged mono channel
 - 4. S/N (20 Hz 20 kHz @ 8 Ohms) > 97 dB
 - a. Contractor shall provide all cabling and mounting hardware to support a fully functioning system.
- H. One (1) Audio Projection Speaker System

- 1. Acceptable Manufacturer(s)
 - a. Harman/JBL
 - 1. JBL SRX835
 - b. Or Equal
- 2. System must contain Two (2) Loud Speakers.
- 3. Loud Speakers shall be permanently mounted with one on each side of the "teaching wall" detailed in Appendix A. Exact location to be determined by Owner.
- 4. System must be capable of 1600 watts of power each
 - a. Contractor shall supply all cables and accessories for a fully functional system.
- 5. One (1) input channel
- 6. One (1) output channel
- 7. Contractor shall supply all necessary mounting brackets and hardware fully functional system to the owners desired location.
- I. One (1) Audio Recording/Playback System
 - 1. Acceptable Manufacturer(s)
 - a. Tascam
 - 1. SSR250N
 - b. Or Equal
 - 2. Audio Recorder shall be mounted in contractor provided audio equipment rack on the "teaching wall". Exact location to be determined by Owner.
 - a. Contractor shall supply all cables and accessories for a fully functional system.
 - 3. One (1) input channel
 - 4. One (1) output channel
 - 5. Contractor shall supply all necessary mounting brackets and hardware fully functional system to the owners desired location.

- 6. Contractor shall configure system for instant recording from contractor provided microphone described herein.
- 7. Contractor shall configure system for instant playback from previously recorded audio.
- J. One Portable Voice Amplification System
 - 1. Acceptable Manufacturer(s)
 - a. Audio Technica
 - b. Shure
 - c. Senheiser
 - d. Yamaha
 - e. Or Equal
 - 2. Three (3) Vocal Microphone(s)
 - a. Contractor shall supply all cables and accessories for a fully functional system.
 - 3. One (1) Analog Audio mixer
 - a. Six (6) Input
 - b. Two (2) Output
 - c. Contractor shall supply all cables and accessories for a fully functional system. Contractor shall include necessary mounting hardware to mount in contractor provided portable av rack described herein.
 - d. Contractor shall supply all cables to connect rack mounted audio mixer described herein.
 - 4. One (1) Portable AV Rack
 - a. Rack shall be Twelve (12) U in size
 - b. Rack shall be on wheels
 - c. Rack shall include a drawer capable of storing 3 microphones and cables described herein.
- K. One (1) Equipment Cabinet

- 1. Acceptable Manufacturer(s)
 - a. Tripp Lite
 - 1. SRW12US33
- 2. Equipment cabinet shall be 12U in size
- 3. Contractor shall supply all necessary mounting brackets and hardware fully functional system to the owners desired location.

2.09 Configuration C

- A. Contractor shall supply one (1) of the specified configurations in each of the following locations.
- B. One (1) Projector
 - 1. Acceptable Manufacturer(s)
 - a. Epson
 - 1. EB-PU2220B
 - 2. 20,000 Lumens
 - 3. Projector shall have a minimum of One (1) HDMI ports for connectivity.
 - 4. Projector shall have on board wireless presentation capability.
 - 5. Contractor shall insure the projector be securely installed and affixed to the wall as shown on Appendix B
 - 6. Projector shall be connected to supplied HDMI input location system receive transmission of signal from supplied input location.
 - 7. Projector shall include all necessary accessories and equipment for a full resolution image on contractor provided projector screen described herein.
- C. One (1) Multi-media Input Faceplate
 - 1. Input location shall be "stage left" on the existing performance platform.
 - 2. All cable, surface mount box, raceway, connectors and necessary components shall be factory manufactured with terminations and connector assemblies fully attached and integral to the cable to industry published quality standards and meet first class performance requirements and as may be specified herein.

- a. Infrastructure cable to connect projector to a wall plate shall be provided.
 - 1. Active HDMI Digital Video Cable 1 shall be of commercial firstclass quality manufacture and meet or exceed the following requirements:
 - a. 4K HDMI Active Optical Cable or Equal
 - b. Supports 4K@60Hz
 - c. CMP Plenum Rated
 - d. Rated for in wall use
- b. Wall plate provided shall be constructed of commercial grade stainless steel.
 - 1. Wall plate shall contain connection points for all specified cables
- c. Cable shall terminate in the following connector gender:
 - 1. Active HDMI Digital Video Cable 1 HDMI Type A 19 pin plug connector to display device.
- d. Extra deep, double gang, surface mount box shall be provided for integration with contractor supplied stainless-steel faceplate.
- A. One (1) Electric Retractable Projection Screen(s).
- 1. Acceptable Manufacturer(s)
 - a. Da-Lite
 - 1. Cosmopolitan Series
 - b. Or Equal.
- 2. Projection surface shall be One-Hundred Ten inches (110") diagonally.
- 3. Projection surface shall be Da-Lite "high contrast matte white" or equal.
- 4. Shall include a Low Voltage Controller for integration contractor provided keyed switch for projector screen control.
- 5. Contractor shall supply all cables and accessories for a fully functional system.

6. Contractor shall supply all materials to mount on the wall as specified on Appendix B

2.10 Configuration D

- A. Contractor shall supply one (1) of the specified configurations in each of the following locations. Reference Appendix C weight room photos.
 - 1. High School Weight Room
- B. One (1) Pendent Style Audio Projection Speaker System
 - 1. Acceptable Manufacturer(s)
 - a. Harman/JBL
 - 1. JBL Control 64P/T
 - b. Or Equal
 - 2. System must contain Eight (8) Pendent Speakers
 - a. Speakers shall be suspended from the ceiling in a manor to provide adequate audio coverage of the given space.
 - 3. System must be capable of 200 watts of power each
 - 4. Contractor shall supply all cables and accessories for a fully functional system.
 - 5. Contractor shall supply all necessary mounting brackets and hardware fully functional system to the owners desired location.
- C. One (1) Amplification System shall be provided and installed
 - 1. Acceptable Manufacturer(s)
 - a. Crestron
 - b. Crown
 - 1. CDI 1000
 - c. Harman/JBL
 - d. Or Equal
 - 2. Two (2) input channels and One (1) output channels

- 3. 275W output per channel
- 4. S/N (20 Hz 20kHz @ 8 Ohms) 97 dB
- D. One (1) Equipment Cabinet
 - 1. Acceptable Manufacturer(s)
 - a. Tripp Lite
 - 1. SRW12US33
 - 2. Equipment cabinet shall be 12U in size
 - 3. Contractor shall supply all necessary mounting brackets and hardware fully functional system to the owners desired location.
 - 4. Contractor shall provide plexiglass cover with cutouts for but not limited to, amplifier power.
- E. One (1) Bluetooth Receiver
 - 1. Acceptable Manufacturer(s)
 - a. Denon
 - 1. DN-300BR
 - b. Or Equal
 - 2. Bluetooth Receiver shall have a minimum of 75' in range
 - 3. Contractor shall supply all necessary mounting brackets and hardware fully functional system to the contractor provided equipment rack.
 - 4. Contractor shall supply all necessary audio cabling for connecting Bluetooth Receiver to the contractor provided audio system.

2.11 ALLOWANCES

A. Contractor shall include allowances for equipment and/or other contract service reimbursements as required below in base bid lump sum amount(s). Equipment and/or contract services shall be provided and sourced at Owner's discretion and convenience with full cooperation by Contractor and paid for from successful bidder's contract in the amount(s) provided for herein. Any allowance amount proving to be excessive for the intended equipment and/or contract services shall be credited to the Owner against contract payment requests.

1. Allowance shall be made in the amount of \$10,000.00 for Owner directed infrastructure upgrades.

PART 3 - EXECUTION

3.01 PREPARATION

- A. Contractor shall conduct detailed walk-through examination with Designer, Construction Manager and Owner verifying equipment and material locations as well as mounting and placement requirements prior to commencement of other installation activities.
- B. Contractor shall ensure all submittals and have been provided to, and approval has been obtained from Designer and Owner prior to commencement of any final installation activities. Submittals shall include, but not be limited to:
 - 1. Shop drawings, data sheets and system diagrams including specific cable connectors and types proposed to be installed.
 - 2. Asset tag format, composition, attachment method and location on each serialized component being provided.
 - 3. Firmware configuration template to be used for each component provided.
 - 4. Written installation, coordination and test procedure to be followed by installing technicians and engineers.
 - 5. Final documentation template.

3.02 INSTALLATION

- A. Contractor shall be familiar with the environment where work will be done as specified herein and make every reasonable effort to minimize interference with Owner's or other contractor's activities.
 - 1. Appendices depicting general ceiling conditions for areas of buildings are included herein. Contractors shall field verify specific room conditions.
- B. Work Areas shall be cleaned at the end of each day. All debris shall be cleared, removed and disposed of off premise. All equipment and tools shall be removed from common areas and stored in approved, secure storage locations.
 - 1. Owner shall not be responsible for disposal or transportation of any packaging materials or other waste items.

- 2. Owner's waste containers including site dumpsters shall not be used for material disposal.
- C. All equipment and materials shall be installed in a neat and workmanlike manner. Best practices installation principles shall be used throughout the project.
- D. The Contractor shall furnish, set in place, and install all equipment necessary for a fully compliant and operational system as specified herein. The installation process includes, but is not limited to the following:
 - 1. Inventory receipt of all components and equipment.
 - 2. Storage of all equipment and components until such time those items are installed according to the specifications.
 - 3. Transport equipment to the Owner's installation location(s).
 - 4. Assemble, install, configure and test all equipment and components, maintaining accurate inventory records and status documents and discarding packaging.
 - 5. Collect all information necessary to accurately program all system devices to the Owner's intended use and need.
 - 6. Label with asset tags and other markings provided by Owner all system devices as may be appropriate and required by Owner and Designer.
 - 7. Work shall be performed to meet local codes and industry standards including proper grounding and bonding of installed equipment. Work shall conform to "best practices" observed by industry professional installers and as required by Owner and Designer.
 - 8. Work shall include careful coordination and cooperation with others to ensure a timely, cost effective and proper installation for Owner's intended application. Such efforts shall include, but not be limited to, coordinating and cooperating with other contractors, Owner, Designer and Engineer.
 - 9. Where cables are to be routed through or on a finished wall, standard connectors must be used at the wall location to terminate call cables. All wall plates shall be stainless steel. Plastic or nylon plates shall not be acceptable. Cables routed out of a wall box on a finished wall without proper standard connection termination shall not be acceptable.
 - 10. All cables shall be proper and adequately supported using hooks or rings no more than eight feet (8') apart. Cables supported by structural steel,

- ceiling grid or hanger wires will not be acceptable. All cable routing shall be neat and orderly.
- 11. All cable connecting components mounted in/on Technology Cart, shall have adequate cable slack to provide for full system inspection and or service without the removal (intentional or inadvertent) of connecting cables, including items that will be placed on the keyboard tray of equipment carts.
- 12. Label all cable connections for intuitive user access and as directed by Owner and Designer.
- 13. Work may include extending cables from installed equipment, and as required and/or specified herein, to Owner identified connection outlets.
 - a. Work includes supply, connection and testing of any such cables.

14. PROJECTORS

- a. Install, configure and test approved firmware configuration template including, but not limited to:
 - 1. Power on Image.
 - 2. Lamp setting.
 - 3. Firmware based Device ID (Including parameters such as: TCP/IP settings, Host Name, etc.).
 - 4. Default port selection.
- b. Contractor shall install and fully configure Epson projector management software and enable projectors for management.
- c. Contractor shall install manufacturer recommended firmware during initial installation.
- d. Neatly configure all cables as directed by Owner.
- e. Attach projector to mount using manufacturer best practices.
- f. Connect AC power using cord provided to projector.
- g. Align projector with Contractor provided screen. Contractor shall install projector in relationship to the screen to maximize the projected image.
- h. Set keystone adjustment(s) as required.

- i. Zoom and focus projector as required.
- j. Secure all adjustment points.

15. VOICE AMPLIFICATION

- a. Provide and connect all audio input and output device cables.
- b. Secure mounting location at projector location with mounting screws or Velcro pads to eliminate involuntary equipment movement.
- c. Neatly route all cabling and secure slack.
- d. Adjust balance levels for standard configuration.
- e. Neatly route all cabling and secure slack.
- E. It shall be the responsibility of the Contractor to repair or replace any damage done to the structure of finishes in the building by the Contractor. If in the course of work, Contractor damages, marks or misplaces any surfaces or access plates/panels the Contractor shall repair and/or replace the surface, plate or panel to the original condition.
 - 1. Repairs shall include, but not be limited to patching and painting.
 - 2. Final determination as to the damage condition and/or repair/replacement fitness of any surface, plate or panel shall be the sole responsibility of the Designer.
 - 3. The building and work area shall be returned to its original condition prior to final sign off of the project.
- F. Following installation and system "turn-up", but prior to final acceptance of the system, Contractor shall conduct follow-up interviews with Owner identified administrators and staff to review system functionality, suitability and confirm feature and program fitness for Owner applications.
 - 1. Follow-up interviews shall be fully documented by Contractor and submitted to Owner for approval.
- G. All cable and device labels shall match existing standard.
- A. Sites of Work:
 - Woodhaven High School 24787 Van Horn Road Brownstown, Michigan 48134

 Patrick Henry Middle School 24835 Hall Road Brownstown, Michigan 48134

3.03 TESTING

- A. In an effort to ensure a smooth "turn-up" of the new system Contractor shall submit to a thorough testing process as defined herein prior to cut-over.
- B. Prior to requesting testing by Designer, the Contractor shall use adequate means to assure the Work is completed in accordance with the specified requirements, meets the owner's specific application requirements and is ready for functionality and integrity testing.

C. Testing Procedures

- Prior to system "turn-up", Contractor shall submit a written request and proposed test plan to Designer indicating they have completed full and final configuration of the system and are ready to have system integrity and functionality tested.
- 2. Within reasonable time after receipt of request, Designer will accept or revise the proposed test plan, provide a test schedule and coordinate testing date(s) with Owner and Contractor.
- 3. Should Designer determine the Work is not acceptably configured or not of adequate integrity:
 - Designer promptly will so notify Contractor, giving reasons therefore and providing sufficient details to allow Contractor to make corrective actions.
 - b. Contractor shall then expeditiously remedy the deficiencies and notify Designer in writing when ready for re-testing.
 - c. Designer will schedule re-test of the Work.
 - d. Excessive re-testing of Work may result in fees being assessed Contractor.
- 4. Should Designer and Owner concur the Work is configured properly and system integrity is as required:
 - a. Designer will review Contractors detailed "turn-up" plan, and upon finding it acceptable issue a memorandum of Testing Completion to Owner and Contractor after which system "turn-up" can proceed.

3.04 DOCUMENTATION

- A. Contractor shall, throughout the completion of the project, provide Owner a file storage system that shall include all necessary equipment, including if reasonably required, file drawers, folders, dividers, etcetera, to contain all asbuilt drawings, owner's manuals of all equipment installed, warranty and maintenance information and other information the Contractor, Designer and/or Owner deem necessary. Documentation shall also be provided in a digital format in file formats and on media as specified by Owner and/or Designer.
- B. Contractor shall be responsible for providing thorough, timely documentation on all hardware, software. Documentation shall include, but not be limited to:
 - 1. Equipment description.
 - 2. Equipment make.
 - 3. Model number.
 - 4. Software release.
 - 5. Date installed.
 - 6. Manufacturer's warranty.
 - 7. Maintenance contract terms.
 - 8. Verification of maintenance contract engagement.
 - 9. Telephone numbers for service and support.
 - 10. Detailed technical support and service procedure instructions.
 - 11. All product (hardware and software) manuals and manufacturer supplied documentation, including, but not limited to owner manuals, system administrator manuals and configuration guides. Where number of duplicate copies for particular manual or documentation item could be reasonably considered excessive, Contractor shall request direction from Owner and Designer.
 - 12. Photocopy of original invoice listing make and model for all components and equipment from individual manufacturer(s), distribution source(s), or authorized agent(s) to establish manufacturer warranty start date for potential use after end of contract warranty provisions.
 - 13. CAD or Visio as built drawings/diagrams for each building.
 - 14. System Configuration Report.

15. Complete inventory of installed hardware and system software including, but not be limited to, model numbers, Ethernet MAC address, serial numbers, physical installation location and software options.

3.05 TRAINING

- A. No training shall be conducted prior to training outline and/or syllabus being approved by Owner, Instructional or overview activities conducted without prior content approval with not be deemed contract training, and Contractor shall remain responsible for delivery of approved training.
- B. Contractor shall provide training for the Owner designated system administrator(s). Owner shall designate up to four (4) administrators to be trained. Training shall be a minimum of two (2), two (2) hour sessions in length, at the convenience of the Owner personnel, and of sufficient duration to satisfactorily complete training on all system administration functions including, but not limited to:
 - 1. Basic trouble shooting of the installed system and components including diagnostic and problem resolution actions.
 - 2. System back-up and restore functions and procedures for all system parameters and configurations.
 - 3. Device additions, moves and changes as well as reconfiguration.
 - 4. Review of system alerts, logs and monitoring of configuration parameters including, but not limited to and system configuration changes.

3.06 SCHEDULE, MEETINGS AND PLANS

A. Schedule

- 1. Contractor Chosen: Week of January 22, 2024
- 2. Work Commences: Week of February 12, 2024
- 3. Substantial Completion: Week of April 8, 2024
- 4. Project Close-out: Week of May 13, 2024
- B. Planned sequence of operations shall be established by the Contractor within the guidelines established by the Owner, as required herein and as required to meet schedules.
- C. All work shall be coordinated with Owner's construction manager on site.

D.	Project progress meetings shall be held, but not limited to, weekly at a site and
	time identified as convenient for Owner and as required herein. Meetings will
	be attended as required herein.

END OF SECTION

GMB

616.796.0200

WWW.GMB.COM

TOWN

4. PROVIDE 120VAC POWER FOR ALL SMOKE DAMPERS AND COMBINATION

D. PROVIDE FIRE ALARM DUCT SMOKE DETECTOR WITHIN 5 FEET OF EACH

DAMPER W/ CORRESPONDING HVAC UNIT(S) PÉR CODE REQUIREMENTS. 5. PROVIDE BOX-COVER FUSIBLE DISCONNECT SWITCH (ON BUILDING INTERIOR IN ACCESSIBLE LOCATION) FOR EACH SMALL (< 1/2 HP) MECHANICAL AND/OR PLUMBING EQUIPMENT MOTOR LOAD WHERE MORE THAN ONE UNIT IS INCLUDE BUT ARE NOT LIMITED TO CABINET HEATERS, DAMPERS, EXHAUST FANS, FAN COIL UNITS, PUMPS, UNIT HEATERS, VAV BOXES, ETC.

7. CONSOLIDATE ALL POWER SUPPLIES REQUIRED FOR ELECTRONIC DOOR HARDWARE (REF. SECTION 08 71 00) TO CENTRAL LOCATION(S) ADJACENT TO DESIGNATED ACCESS CONTROL EQUIPMENT LOCATION(S). CONNECT ALL POWER SUPPLIES TO DEDICATED [LOCAL] [STANDBY POWER SYSTEM] BRANCH CIRCUIT(S) AS DESIGNATED [FOR CONTINUED OPERATION UNDER LOSS OF UTILITY POWER].

	ELECTRICAL KEYNOTES
C01	CONTRACTOR TO REINSTALL PROTECTED DEVICE IN THIS LOCATION
P03	RE-WORK AND EXTEND EXISTING CIRCUIT TO NEW EQUIPMENT, INCLUDING SUPPORTS, CONDUIT AND CONDUCTORS.
P13	PROVIDE AND INSTALL NEW 200A/3P CIRCUIT BREAKER AND CIRCUIT FOR NEW EQUIPMENT.
P16	RE-WORK AND EXTEND CIRCUITS FOR NEW KITCHEN EQUIPMENT. PANEL L29 (DOUBLE TUB). ALL EQUIPMENT RECEPTACLES SHALL BE GFCI CIRCUIT BREAKERS. GENERAPURPOSE RECEPTS SHALL BE DEVICE GFCI TYPE.
P17	RE-WORK AND EXTEND CIRCUITS FOR NEW KITCHEN EQUIPMENT IN SIMILAR LOCATION. FOR REPLACED EQUIPMENT IN NEW LOCATION, PROVIDE NEW CIRCUIT, RE-USE PATHWAYS AS POSSIBLE. PANEL X17, X19, X11. TRACE AND MARK ALL CIRCUITS TO REMAIN. ALL EQUIPMEN RECEPTACLES SHALL BE GFCI CIRCUIT BREAKERS. GENERAL PURPOSE RECEPTS SHALL BE DEVICE GFCI TYPE.
P18	RE-WORK AND EXTEND EXISTING PROJECTOR CIRCUIT TO

Projector Location

☐ Loudspeaker Location


Multimedia Input Location

11.09.2022 BIDS & CONSTRUCTION
12.07.2022 ADDENDUM 002
12.19.2022 CONSTRUCTION SET

PROJECT NO. NO PART OF THIS DRAWING MAY BE USED OR REPRODUCED IN ANY FORM OR BY ANY MEANS, OR STORED IN A DATA BASE OR RETRIEVAL SYSTEM, WITHOUT PRIOR WRITTEN

UNIT 'S' FIRST FLOOR POWER & COMMUNICATIONS PLAN

APPENDIX A



UNIT 'S' FIRST FLOOR POWER & COMMUNICATIONS PLAN

1/8" = 1'-0"

FIRE/SMOKE DAMPERS.
A. [REFER TO MECHANICAL/HVAC DRAWINGS FOR LOCATIONS AND

QUANTITIES OF DAMPERS.]

B. CONNECT TO DEDICATED 20A BRANCH CIRCUIT (WITH BREAKER LOCK-ON ACCESSORY) IN LOCAL PANELBOARD FOR DAMPER(S) IN EACH AREA (DAMPERS MAY BE GROUPED ON EACH CIRCUIT).

C. TERMINATE W/ BOX-COVER FUSIBLE DISCONNECT SWITCH AT EACH DAMPER (UNLESS COVERED BY ANOTHER DUCT DETECTOR WITHIN 5 FEET).

CONNECTED TO A COMMON BRANCH CIRCUIT. TYPICAL EQUIPMENT TYPES

E. PROVIDE FIRE ALARM ADDRESSABLE RELAY(S) FOR INTERLOCKING

6. DESIGNATED CABLING PATHWAYS (CONDUITS, CABLE TRAYS, PENETRATION SLEEVES, ETC.) SHALL BE RESERVED FOR DIV. 27 COMMUNICATIONS CABLING AND DIV. 28 SAFETY/SECURITY CABLING ONLY. OTHER CABLING TYPES, SUCH AS DIV. 23 CONTROLS, DIV. 26 CONTROLS, AND ARCHITECTURAL EQUIPMENT CABLING SHALL BE SUPPORTED AND SLEEVED BY OTHER INDEPENDENT PATHWAYS, HANGERS, AND SUPPORTS.


NEW LOCATION.

DRAWN NTM REVIEWED PRH


GMB COPYRIGHT® 2022 ALL RIGHTS RESERVED

KEYPLAN

Appendix B







ISSUE DATE	ISSUED FOR
10/28/2016	BIDS
Ī	-
<u> </u>	•
	-
<u>L</u>	-
<u> </u>	-
<u></u>	-
	-
	-
	-
DRAWN	KRM
CHECKED	KRM
APPROVED	DCJ

FRENCH associates

236 Mill Street Rochester, MI 48307

PROJECT

Woodhaven Schools
Bid Pack #2
Patrick Henry Middle
Renovations

Woodhaven, Michigan

COMPOSITE
FIRST FLOOR PLAN
CODE PLAN

2015-090

SHEET NUMBER

12.01

48307 T 248.656.1377 F 248.656.7746 © FRENCH ASSOCIATES, INC.

EXISTING BUILDING AREA REMAINS UNCHANGED

CODE PLAN INFORMATION

PROFESSIONAL IN RESPONSIBLE CHARGE.

3) DEFERRED SUBMITTALS (106.3.4)

SMOKE DETECTION SYSTEM.

COMPLIANCE METHOD.

GENERAL (SECTION 801)

THE IBC. (SECTION 602)

MICHIGAN REHABILITATION CODE FOR EXISTING BUILDINGS 2012

2) DESIGN PROFESSIONAL IN RESPONSIBLE CHARGE (106.3.4)

DEFERRED SUBMITTALS WILL INCLUDE THE FOLLOWING:

4) USE AND OCCUPANCY CLASSIFICATION (CHAPTER 4)

A. WORK SHALL ALSO COMPLY WITH ALTERATION-LEVEL 1

(UNLESS LESS THAN 5% INCREASE) (SECTION 606).

REQUIRED THROUGHOUT IN ACCORDANCE WITH:

B. EXIT SIGNS (805.8)- NEW EXIT SIGNS ARE PROVIDED.

A. EXISTING PUBLIC TOILET ROOMS ARE ACCESSIBLE.

ARE IN ACCORDANCE WITH SECTION 807.

6) CHANGE OF OCCUPANCY (CHAPTER 10)

9) RELOCATED OR MOVED BUILDINGS (CHAPTER 13)

RELOCATING OR MOVING THIS BUILDING.

A) 2012 MICHIGAN MECHANICAL CODE

B) 2012 MICHIGAN PLUMBING CODE

C) 2014 NATIONAL ELECTRICAL CODE

D) 2012 NFPA 101 LIFE SAFETY CODE

WORK DOES NOT EXCEED 50% OF THE FLOOR AREA.

BUILDING USE GROUP IS EDUCATIONAL GROUP E.

5) ALTERNATIONS- LEVEL 2 (CHAPTER 8)

SUBMITTALS BY THE CONTRACTOR.

MEANS OF EGRESS (SECTION 805)

LIGHTING IS PROVIDED.

4. ACCESSIBILITY (SECTION 806)

5. STRUCTURAL (SECTION 807)

6. ELECTRICAL (SECTION 808)

7. MECHANICAL (SECTION 809)

8. PLUMBING (SECTION 810)

REMAINING THE SAME.

) ADDITIONS (CHAPTER 11)

ADDING ANY ADDITIONS.

HISTORIC BUILDING.

10) OTHER CODES

A REPRESENTATIVE OF FRENCH ASSOCIATES WILL BE THE DESIGN

A) CONSTRUCTION DOCUMENTS FOR FIRE ALARM SYSTEMS. INCLUDING DUCT

THE PROJECT WILL HAVE LEVEL 2 ALTERATIONS AND IS USING THE WORK AREA

1.) NEW INTERIOR FINISHES SHALL COMPLY WITH FLAME SPREAD REQUIREMENTS OF THE IBC AS WELL AS RADIANT FLUX REQUIREMENTS OF

B. STRUCTURAL PROVISIONS SHALL APPLY FOR NEW ROOFING, SUPPORT OF NEW ROOFTOP MECHANICAL EQUIPMENT AND NEW ELEVATOR SHAFT

FIRE PROTECTION (SECTION 804) AN AUTOMATIC SPRINKLER SYSTEM IS NOT

. SECTION 804.2.2: GROUP A DOES NOT MEET THE CONDITION NO. 2. THE

SECTION 804.4.1.1: A FIRE ALARM AND DETECTION SYSTEM IS BEING PROVIDED AND INSTALLED. MODIFIED. THESE WILL BE DEFERRED

A. MEAN OF EGRESS LIGHTING (805.7)- NEW COMPLIANT MEANS OF EGRESS

A. THE LIMITED STRUCTURAL ALTERATIONS WE ARE MAKING TO THIS FACILITY

A. ALL NEW SYSTEMS COMPLY WITH 2011 MICHIGAN ELECTRICAL CODE.

A. ALL NEW SYSTEMS COMPLY WITH MICHIGAN MECHANICAL CODE 2012.

A. ALL NEW SYSTEMS COMPLY WITH MICHIGAN PLUMBING CODE 2012.

REQUIREMENTS OF CHAPTER 10 DO NOT APPLY DUE TO THE OCCUPANCY

REQUIREMENTS OF CHAPTER 11 DO NOT APPLY BECAUSE WE ARE NOT

B) <u>HISTORIC BUILDINGS (CHAPTER 12)</u>
. REQUIREMENTS OF CHAPTER 12 DO NOT APPLY BECAUSE THIS IS NOT A

. REQUIREMENTS OF CHAPTER 13 DO NOT APPLY BECAUSE WE ARE NOT

D) ICC/ANSI A117.1-2003 ACCESSIBLE AND USABLE BUILDINGS AND FACILITIES

WORK AREA COMPLIANCE METHOD: LEVEL 2 ALTERATIONS

STUDENT POPULATION IS NOT CHANGING

NO CHANGE OF USE

NO CHANGE OF USE

THE BUILDING IS FULLY SPRINKLED.

ALTERATION DESCRIPTION:

INTERIOR RENOVATION OF LGI ROOM AND MEDIA CENTER: CARPET, PAINT AND NEW CEILING.
NEW CEILING IN CAFETERIA.

REPLACEMENT OF PORTION OF THE EXISTING CORRIDOR VCT WITH NEW VCT. NEW FINISHES IN THE EXISTING BATHROOMS.

MINOR ELECTRICAL AND MECHANICAL UPGRADES.

