



**RFP 25-0045**

**Southeastern High School CTE Annex – District Technology Infrastructure Additions**

**Questions and Answers**

- Q: For the fiber, under “Work Included” an indoor / outdoor, armored OM3 fiber is requested but under “Manufacturers” it says Indoor Plenum. Is this to be indoor / outdoor or indoor plenum?
- A: It is Indoor/ Outdoor rated 6 strand OM3 50 micron armored MMF fiber.
- Q: For the fiber patch cords under “Manufacturers” it says to provide Singlemode cables. Are we to provide OM3 or OS1 cables?
- A: Please Provide OM3 LC to LC.
- Q: In the “Installation” section there is direction for yellow armored cable or innerduct, which typically signifies singlemode fiber. Do you want single or multi-mode fiber?
- A: Please see the answer above.
- Q: Is there existing raceway for the fiber? If not, can it be supported with j-hooks every 5-6’?
- A: There may be an existing raceway available that can be used, but Suppliers should plan to install new raceway/ supports on an as needed basis. J- hooks are acceptable but may not be installed at intervals greater than 5’.
- Q: Is this a new area, or are we to assume working off-shift?
- A: Please see the "INSTALLATION" section of all bid categories.
- Q: Is there existing raceway for the copper? If not, can it be supported with j-hooks every 5-6’?
- A: Please review the LOW VOLTAGE CABLING- PART 3- 3.02- D-7 of the RFP.
- Q: Do you have a sign in sheet or list of contractors that attended the pre-bid meeting for the RFP referenced above? If so, do you mind sharing it with us?
- A: Please see the attendance sheet attached to this document.
- Q: Would it be possible to obtain the pre-bid meeting attendance sheet for the subject solicitation?
- A: Please see the above answer.

**Students Rise.  
We all Rise**

DPSCD does not discriminate based on race, color, national origin, sex, disability and/or religion. Contact Compliance for more information at (313) 240-4377 or [detroitk12.org/admin/compliance](http://detroitk12.org/admin/compliance).



## Procurement Department

Fisher Building • 3011 West Grand Blvd., 11th Floor • Detroit, MI 48202

[Detroitk12.org](http://Detroitk12.org)

Q: The data drops being placed in “wall boxes”: Will the conduit in the wall and box be provided by others?

A: Yes.

Q: For the fiber run: We see the MDF and IDF on the provided drawings, however there is not a visual for where the new addition connects to the existing structure. Do you have this documentation so we can get fiber footage?

A: There will be a pathway provided from the new IDF to the ceiling space inside the main building; see Addendum 2.

**Students Rise.**

**We all Rise**

DPSCD does not discriminate based on race, color, national origin, sex, disability and/or religion. Contact Compliance for more information at (313) 240-4377 or [detroitk12.org/admin/compliance](http://detroitk12.org/admin/compliance).

25-0045 Southeastern CTE Technology Infrastructure Additions Pre-Bid

| Name | Company              | Contact Information |
|------|----------------------|---------------------|
| Mike | Learning Consultants | (313) 717-1510      |