

Project Q & A

Project Owner:	Southfield Public Schools	
Project Name:	Access Controls Upgrades	
Issue Date:	September 19, 2024	

Project Questions and Answers:

This document provides answers to questions asked by bidders who have reviewed the Technology Request for Bid for the above referenced project.

Q1	I noticed in the RFP, there are 14 sites, but there's only 10 drawings. Are there drawings for each individual site?	
A 1	Reference Appendix B, C, D, and E.	
Q2	I see we're moving the existing card readers from the Vanderbilt platform to the Genetec platform. Do you know what kind of Card Readers the current system is using? HID, Signo, etc.	
A2	The standard card reader is XceedID PR10.	
Q3	Who is supplying the locking hardware?	
А3	For Appendix B, locking hardware shall be provided by security integrator. For Appendix C, D, and E, locking hardware shall be provided by construction door hardware contractors.	
Q4	Who is cutting the doors to fit the locking hardware?	
A4	For Appendix B, doors shall be cut to fit locking hardware by security integrator. For Appendix C, D, and E, doors shall be cut to fit locking hardware by construction door hardware contractors.	
Q5	Which doors are getting door releases?	
A 5	Reference Appendix C, D, and E.	
Q6	Any video intercoms to be added or upgraded?	
A6	There are not any identified as part of this project.	

Bid ID: 3044	Communications by Design, Inc.
Questions and Answers Issued: October 3, 2024	Proprietary Information – All Rights Reserved



Q7	Are there drawings for Site #6, #7, and #13? If not, what are the counts for these locations? There is a drawing for Bussey Center. The building address is 24501 Fredrick St, Southfield, MI 48033, but there's nothing in the RFP about it. Why was this drawing included, but the site is not listed in the Sites of Work?	
A 7	Reference Appendix B, C, D, and E. See Addendum #2	
Q8	What kind of Genetec system is currently in place?So we can expand it.	
A8	There is not a Genetec system currently in place.	
Q9	Are you using mobile credentials?	
А9	Mobile credentials are not currently being used.	
Q10	Can you explain the Panic buttons? You want them integrated with access control or with the alarm system?	
A10	The "panic button" should be integrated with the access control system.	
Q11	Do we need to include a lift at each site?	
A11	The need of a lift for this work shall be determined by the contractor.	
Q12	What kind of Video system do you currently have?	
A12	Milestone	
Q13	What kind of intrusion alarm do you have?	
A13	Honeywell Vista	
Q14	Has any of the locations transitioned the card readers from the vanderbilt set up, to the Genetec setup? What type of card readers replaced the old ones?	
A14	The system has not transitioned from Vanderbilt.	
Q15	Who is providing the locking hardware? Security integrator, or Door Contractor?	
A15	For Appendix B, locking hardware shall be provided by security integrator. For Appendix C, D, and E, locking hardware shall be provided by construction door hardware contractors.	
Q16	Who is cutting the doors and frames to fit the electric strikes and latches?	
A16	For Appendix B, doors shall be cut to fit locking hardware by security integrator.	

Bid ID: 3044	Communications by Design, Inc.
Questions and Answers Issued: October 3, 2024	Proprietary Information – All Rights Reserved



are by	
The majority of exterior doors are solid.	
d E will have	
There are not any identified in the project at this time.	
s. Card Reader	
sidered for this	
l Management	

END OF QUESTIONS AND ANSWERS #1

Bid ID: 3044	Communications by Design, Inc.
Questions and Answers Issued: October 3, 2024	Proprietary Information – All Rights Reserved